NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

HIRANANDANI COMMUNITIES
Mumbai
Maharashtra -India.

Date : 17.10.2020
Quote NO : SQT.20-21_0055R2
Kind Attn : Mr. SILAMBHARASAN. P
Email Id : psilambarasan@hrealty.com
Contact No: 8939828669

Subject : Quotation for Sliding Gate & Boom Barrier

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	AUTOMATIC SINGLE LEAF BI-PARTING SLIDING GATE	17000	1800	1	5,96,000	5,96,000	20,000	20,000
2	AUTOMATIC SINGLE LEAF SLIDING GATE	9000	1800	1	3,28,000	3,28,000	15,000	15,000
3	AUTOMATIC SINGLE LEAF SLIDING GATE	6000	1800	1	2,68,000	2,68,000	15,000	15,000
4	AUTOMATIC BOOM BARRIER	8000		2	2,23,000	4,46,000	15,000	30,000
5	AUTOMATIC BOOM BARRIER	6000		1	1,02,000	1,02,000	15,000	15,000
6	AUTOMATIC BOOM BARRIER	4500		2	97,000	1,94,000	15,000	30,000
			Total Value			**19,34,000**		**1,25,000**
7			**P&F Charges**	0%		-		
			Total Without Taxes			**19,34,000**		**1,25,000**
			GST Extra @ 18%	18%		3,48,120		22,500
			Total With Taxes			**22,82,120**		**1,47,500**
8			Transportation Charges			**Included in above price**		
9			Unloading Charges @ Site			**NIHVA Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Technical Specifications

Sr. No	Description	Specifications
1	Door type	Motorised Sliding Gate
2	Clear Opening gate dimension	1) (W) 17000 mm X (H) 1800 mm 2) (W) 9000 mm X (H) 1800 mm 3) (W) 6000 mm X (H) 1800 mm
3	Opening Direction	Horizontal - from left to right or reverse
4	Mounting Location area	Inside area
5	Design Pattern	Standard Tubular Design Pattern
6	Opening Speed	9 MTR / MINUTE
7	Outer Frame Tube Sizes	80 x 80 x 3.2mm MS SQ. TUBE
8	Internal Vertical Tube Sizes	30 x 30 x 3.20mm MS SQ. TUBE
9	For Post	80 x 80 x 3.2mm MS SQ. TUBE
10	Gap Between Tubes	125mm
11	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
12	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings
13	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
14	Painting	Two Coats of Epoxy Primer and Two Coats of PU Enamel Paint
15	Motor	100% Imported from Europe
16	Safety Standard	1. Photocell 2. Flashing Light
17	Push Button Details	3 PUSH BUTTON TYPE PENDENT (FORWARD, REVERSE & STOP)
18	Emergency Operation	Manual opening in case of power failure
19	Protection Level - IP Rating	IP 24
20	Power Supply	SINGLE PHASE

Boom Barrier

Sr. No.	Description	Specifications
1	Size	8/6/4.5 Mtr
2	Height of Boom from ground	830 MM
3	Make	Nice/BFT
4	Opening time	Opening Time- 8S/6S/4S
5	Motor Power Supply	24V
6	Boom Material & Finish	ALUMINUM
7	Protection Level - IP Rating	IP 54
8	Type of limit Switch	Electronic
9	Safety	Photocell sensor
10	Operation	Push Button Pedant
11	Movable support at other end considered	for 6 mtr and 8 Mtr Boom Barrier only
12	Manual Operation in case of Power failure	customized key
13	Power Requirement	230V±10% 50/60Hz(*)

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	NIHVA Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope
8	Lifting Equipements	In Client Scope

D) Terms & Conditions

Price : Ex Works Chennai

Delivery : **Supply :** 4 to 5 weeks from confirmed purchase order, Advance Payment & Drawing approval.
Installation : If site is ready by 100% we will complete the Installlation in 15 to 20 Days

Payment : 1) Supply - 30% Advance against ABG and 70% Against Delivery.
2) Installation - 100% After Installation and 5% retension on Installation till DLP period.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd