NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Hotel Greenpark
Hyderabad -500016
Telangana

Date : 10.09.2019
Quote NO : SQT.19.20.2044
Kind Attn : Mr. Raj Kiran
Email Id : pur1.corp@hotelgreenpark.com
Contact No: **8008250303**

Project Name & Location: Hotel Greenpark ; Hyderabad, Telangana

Subject : Quotation for Revolving Glass Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Height (mm)	Clear Width (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Automatic Revolving Door (Besam-ASSA Abloy)	3000	3000	1	2,300,000	2,300,000	Inclusive	
2	Automatic Revolving Door (Besam-ASSA Abloy)	2400	2600	1	2,075,000	2,075,000	-	
				Total		**4,375,000**		-
3	P&F Charges			3%		**131,250**		
	Total Without Taxes					**4,506,250**		-
	GST Extra @ 18%			18%		811,125		-
	Total With Taxes					**5,317,375**		-
4	Transportation Charges					**In Client Scope**		
5	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

General Details	**Door 1**	**Door 2**
Internal Diameter	3000mm	2600mm
Internal Height	3000mm	2400mm
Total Height	3200mm	2600mm
Fascia Height	200mm	200mm
Revolving Doorset	2 Door Leaves	
Emergency Stop	1 no. Stop Button	
Design - Outer walls (& NCD if Included)	Besam Frame Profile	

2. Outer Wall	
Finish	Outer walls(& NCD if Included)-Satin Silver Anodised E6-EV1

3. Rotating Section	
Glass Ceiling Console	Standard 45 mm trim with surface mounted Sensors

4. Accessories	
Ceiling	Structural Glass 16.76 mm 1B1 Clear laminated
Outer Wall leading mullion	ESPE monitored presence detection and active PSPE Safety Nosing
Door Set Bottom rail safety	Monitored
Protective Edge in Rubber Safety nosing Control Console	Flush Mounted control with in full height control Post to inner leading mullion
Ceiling Rain Guard	Perimeter Trim upstand over entrance to deflect water run off to the other walls
With center floor plate	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipments are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 - 12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333**

With Best Regards
Filina
7410179333
For NIHVA Technologies Pvt Ltd