Item	Description	Qty	Unit	Rate QR	Amount QR
	CEILING FINISHES				
	GENERAL NOTES				
A	This section of the Bills of Quantities shall include all works required for completion of the "Ceiling Finishes" to the designated areas. Notwithstanding what is included in the descriptions, the unit rates / total rates shall be deemed to include everything necessary for the works herein		Note		
B	Ceiling Finish Types shall be in accordance with Drawings, Schedules and Specifications		Note		
	SUSPENDED BOARD CEILING SYSTEM				
	Gypsum board ceiling system; on and including metal frame suspension system; including thermal and sound insulations, forming, openings, cutting, beadings, trims, sealing edges; fixed to concrete soffit as per drawing and specifications				
C	Gypsum board ceiling; 12.7 mm thick; including sidings, bulkheads; type; C01; (applied paint measured separately)	38	m2		
D	Black gypsum board ceiling; 12.7 mm thick; type; C03	1	m2		
	ALUMINIUM CEILING SYSTEMS				
	aluminium ceiling system with suspension grid, hangers, edge, trims, and all accessories, as per approved drawings and specifications, including complete fixing and finishing.				
E	Linear aluminium ceiling; 25x100mm; type; C02	16	m2		
F	Open cell aluminum ceiling; type; C04	43	m2		
G	Steel structure with aluminium cladding; type; C05	193	m2		
	FABRIC CEILING				
	Retractable fabric ceiling system, including fabric panels, tracks, support framework, and all necessary accessories, as per approved drawings and specifications, with complete fixing and finishing.				
H	Retractable fabric ceiling finish; type; C06	198	m2		
			To Collection QR		