APPLICATION OF BEES WAX OR WAX POLISH :-

The polish shall be applied evenly with a clean soft pad of cotton cloth in such a way that the surface is completely and fully covered. The surface is then rubbed continuously for half an hour. After well rubbing in one coat of wax polish, the work shall be covered with dust proof sheet (cloth for preventing dust falling on the work). Subsequent coat shall be applied after the surface is quite dry and shall be rubbed off with soft flannel until the surface has assumed an uniform gloss and in dry, showing no sign of sickness. The final polish depends largely on the amount of rubbing which shall be continuous and with uniform pressure, with frequent changes in the direction.

SYNTHETIC ENAMEL PAINT

Providing two coats of synthetic enamel paint of approved make colour over one coat of primer on plastered surfaces, wooden surfaces and steel surfaces. A filles putty coating has to be given after primer coat in the case of wooden surfaces. The putty shall be made from pure whiting mixed to the proper consisting with new linseed oil. A little white lead being mixed to help hardening of putty. On no account putty is to be used before primary coat.

Primers to be used shall be according to the manufacturer's specification.

DOUBLE WALL MOTORIZED ROLLING SHUTTER :

TECHNICAL SPECIFICATIONS

- Double wall motorized insulated rolling shutter with guide rail, bottom plate winding shaft and side brackets..
- The shutter Shall comply with IS 6248 : 1979, BS 476 part 22.
- Shutter curtains insulated double wall interconnected galvanized steel.
- Bottom profile with aluminium extruded box profile made of EPDM profile for a sealed bottom door edge..
- Winding shaft to have primer coated steel tube with welded in shafts on both the sides for drive and bearing..
- Steel Side brackets made of M.S plates with stiffeners bearings and hardwares.
- Any minor civil works and electrical wiring works shall be included in the scope.

  The rolling shutters shall include necessary locking arrangement and handles, motorized system with suitable standard make motors, reduction gear box and necessary fitting and fixtures etc. These shall be suitable for fixing in the position as specified. These shutters shall be electrically operated motorized system with necessary accessories.

SINGLE WALL MOTORIZED ROLLING SHUTTER :

TECHNICAL SPECIFICATIONS

- Single walll motorized rolling shutter sections made of mild steel 18 gauge with guide rail, bottom plate winding shaft and side brackets..
- The shutter Shall comply with IS 6248 : 1979, BS 476 part 22.
- Shutter curtains with interlocking slats
- Bottom profile with mild steel with stiffening angle..
- Winding shaft to have primer coated steel tube with welded in shafts on both the sides for drive and bearing..
- Steel Side brackets made of M.S plates with stiffeners bearings and hardwares.
- Any minor civil works and electrical wiring works shall be included in the scope.

  The rolling shutters shall include necessary locking arrangement and handles, motorized system with suitable standard make motors, reduction gear box and necessary fitting and fixtures etc. These shall be suitable for fixing in the position as

specified. These shutters shall be electrically operated motorized system with necessary accessories.

CHAIN LINK FENCE SYSTEM / WELD MESH PANEL

Scope : Providing, fabricating and fixing in position of chain link metal fence system consists of the following –

Planning / preparation : Before commence the work, the route of fence shall be set out by constructing the necessary pillars to the alignment, profile and the site clerance such as clearing shrubs, roots, growths, small trees, bushes also to be taken up.

Foundation : Shall comprise of PCC 1:4:8 base concrete of 100mm thick for foundation of GI box section post at 3000mm intervals alongwith M25 grade cement concrete foundation to a required profile, size of 600mm x 600mm x 600mm including necessary form work, excavation to the required size in all kinds of soil to the required line / alignment / levels as directed by Project Manager including shoring and strutting wherever if necessary.

Trench refilling : After curing / completion of foundation, the trench sides shall be filled with the selected available earth and the conslidation shall be carried out in layers of 15cms depth with necessary watering.

Super structure :

Chain Link Fence – Chain link mesh panels consists of 16mm dia M.S post embedded in cement concrete foundation at 2500mm intervals fabricated with the frame work made out of ISA 75mm x 75mm x 6mm GI box section with frame made out of 50 x 50 mm L angle welded with 25 mm x 25 mm hot dipped galvanized chain link mesh (14 gauge) with necessary holdfast as detailed in drawing. An additional bracing T angle shall be fabricated at the center of the panel.

Weld Mesh – Same as above said but the chain link panels shall be replaced by GI weld mesh panels made out of 3mm / 5mm wire fabricated at 25 x 25mm c/c as mesh fixed with U clips anchor with bolts as indicated in the drawing including hot dip galvanizing, anchoring arrangments, hardwares etc.

Clearing of surplus materials : On completion of fence work, the surplus earth or debris accumulated during the course of construction shall be cleared / levelled to match the FFL as directed by the Project Manager.
Galvanizing : All fabricated fence system shall be galvanized to the shade approved by the Project Manager.

STEEL FABRICATION WORK

Notes **:** *Unless otherwise specified the scope of Steel Fabrication works shall inclusive of the following as the part of technical contract terms :*

a) Straightening, cutting, fabricating, conveying to work site, hoisting and fixing in position.

b) The cost of all materials and labour.

c) Work at all heights, levels and situations.

d) Providing necessary scaffolding, staging, platforms, ladders etc. and removing.

e) Hire charges for necessary hoisting equipments like crane, chain pulley blocks, derricks, winches, screw jacks, hooks, wire ropes etc.

f) All necessary fixtures like bolts, washers and nuts.