Minebea intec
The true measure

Sartorius Mechatronics India Pvt Ltd | 560 058 Bangalore

M/s. Shekhar Saad

M/s. NIHVA Technologies Pvt. Ltd
187, G-Block, 1st Floor, Thermax Chowk,
MIDC,above Renault Showroom,
Chinchwad, Pune - 411019.

Mobile : +91 903144005
E-mail : shekharsaad@gmail.com

Contact Prashanth Gowda

Tel. +91 80 67200 216
Fax. +91 80 67200 100
Mobile +91 9900605684
Email prashanth.gowda@minebea-intec.com

Ref. SMI / WR / PG / Nihva/01 / Rev0
Date. 10th May 2017

Subject : Offer for Checkweigher for ITC Spices project.

Ref : Our Offer SMI / WR / PG / Nihva/01 / Rev0 Dt.10/05/2017 & Our discussion

Dear Sir,

We thank you for your enquiry.

Further to above we are pleased to submit our offer for Checkweighing System for your kind perusal.

We are sure that the offer is in line with your requirement. Should you have any doubt, please feel free to contact us.

We assure you our best of our attention and services. Thanking you.

Yours sincerely,

For **Sartorius Mechatronics India Pvt. Ltd.,**

Prashanth Gowda
Manager – Inspection Technology

Techno Commercial Proposal

A. User Requirement Specification For Checkweighing System :

Line. No.	Products	Product Dimensions (mm)			Gross Wt (gm)	Throughput (pcs/min)	Pitch of products (mm)	Speed Of Conveyor (m/S)
		Length	Width	Height				
1	Powder	200	150	70	1200	120	Not Known	Not Known

Sr. No.	Parameter	UOM	Tube line
1	Type		Chilli & Turmeric Powder
2	Packing		Poly Pouch
3	L (In Dir. Of Transport) X W X H	mm	As indicated above
4	Gross Weight	g	As indicated above
5	Min. Pitch (At Present)	mm	As indicated above
6	Throughput	pcs/min	As indicated above
7	Temperature	ºC	Ambient
8	Reject Limits	g	± 3
9	Belt Width	mm	200
10	Conveying Level	mm	850
11	Present Belt Speed	m/sec	As indicated above
12	Quantity	Nos	1
13	Product Orientation (Assumed)		Length Wise

Minebea intec
The true measure

Based On Above we offer following Checkweigher:

Sr. No.	Parameter	UOM	Specifications
1	Model		Econus 3000
2	Weighing Range	g	2-3000
3	Overall Length	mm	Approx 1200 ± 100
4	Belt Speed	m/sec	0.2 To 1
5	Belt Width	mm	200
6	Transport Height	mm	880 ± 25
7	Direction Of Transport		R/L
8	W&M Approved		Yes
9	Moisture / Spray		No
10	Type Of Cleaning		Dry
11	IP		54

Technical Notes :

1. Accuracy is dependent on following factors :
    a. Environment (Air current, vibration, change in temperature etc.,)
    b. Throughput
    c. Type of packing
    d. Quality of packing.
2. The Consistent Pitch and orientation of the product are very essential for reliable checkweighing same should be maintained at 472 by purchaser.
3. Please note that the maximum speed of the checkweigher can be 1 m/s.
4. The rejection mechanism will be "Pneumatic Pusher" common for both over weight and underweight rejection.

A: Technical Details Of Checkweigher Offered:

Sr.No.	Description	Qty
A-1	AUTOMATIC CHECKWEIGER Model : Econus 3000 completely made of stainless steel, composed of: ELECTRONIC CONTROL SYSTEM for the operation, adjustment and control of the weigh system and for the display and 100 % evaluation of the weight values. • ECI-based control unit for operation and display, in standard housing • A high-contrast, bright LCD-colour graphics display shows the weight value, the class result and all the vital production data without interruption • Quick & easy operation via direct selection keys • Product library for 50 articles • Independently adjustable transport speeds filed in the article data record • A reflection light barrier triggers the weighing cycle, monitors the spacing between products and controls the automatic zeroing WEIGHER STAND WITH CONTROL CABINET • The solid stand housing with IP 54 protection. • Carries a crossbeam, to which the weighcell and the conveying system consisting of infeed, weigh and discharge conveyor are attached • The crossbeam adjusts to the respective working height between 600 and 1000 mm, with feet adjustment range ± 25 mm. Height to be specified while ordering. • Control cabinet with ECI electronics, external motor control (optional), main switch • Power supply: 230 V, 50 Hz, single Phase. Power Consumption approx 450 VA Weighing Sensor High-precision, overload-protected strain-gauge load cell.	01 No.

<table>
<tr><th>Sr.No.</th><th>Description</th><th>Qty</th></tr>
<tr><td>A-2</td><td>TRANSPORT SYSTEM WITH WS 3000 g

Infeed, weigh and outfeed conveyor:

<table>
<tr><th>Conveyor</th><th>Axel Centre (mm)</th><th>Belt Width (mm)</th></tr>
<tr><td>Infeed</td><td>400</td><td>200</td></tr>
<tr><td>Weighing</td><td>400</td><td>200</td></tr>
<tr><td>Outfeed</td><td>400</td><td>200</td></tr>
</table>

Each conveyor has its own 24 V DC back-geared motor

Conveyor belt: belt, quick-acting belt slackener, foodsafe-plastic tension and head pulleys, 30 mm diameter.

Cover over weighing conveyor to protect against wind</td><td>01 No.</td></tr>
</table>

Sr.No.	Description	Qty
O-1	REJECTING DEVICE A Pneumatic Pusher for rejection is supplied with the Checkweigher. Air supply to be provided by Purchaser.	01 No.

Sr.No.	Description	Qty
`O-2	3-FOLD ILLUMINATED SEMAPHORE with Advanced Belt Controls For the visible signalisation of the class results of the checkweigher corresponding to underweight, correct weight and over weight Mounting plinth with tube and three light elements, mounted on top of the electronic cabinet of the checkweigher Easy accessible additional belt controls on the control panel with Emergency stop	01 No.

Basic Unit Price for above Item , Ex-Works, Un-Packed : Rs.5,20,000 /-

(Rupees Five Lacks Twenty Thousand Only)

S: Installation & Commissioning:

Sr. No.	Description
S- 1	Services For : Supervision Of Installation & Commissioning Charges For One System

Basic Price for Item S-1: 15,000/-

(Fifteen Thousand only)

Minebea intec
The true measure

Scope Matrix:

A. Buyer´s :

1. To provide all technical details/drawings that has impact on the working of the systems and / or asked by M/s. Sartorius Mec from time to time.
2. Accept and unload the supplies when received. To acknowledge supplies on the copy of our Invoice / Delivery Challan. The halting costs charged by the transporter / local authorities will be borne by customer.
3. Make sure that the goods are stored properly and ensure that proper security arrangements are made available for the place of storage of equipment.
4. To arrange to shift to the location of the installation, if unloaded in different place.
5. To give atleast 15 days notice to M/s. Sartorius for deputation of our engineer for supervision of installation and commissioning.
6. To erect the system as advised by our technical team, before our engineers visit your site for commissioning.
7. All civil, mechanical, electrical construction and /or modification of existing site, panels, earthing, cabling & conducting. Civil construction including Earth Pits shall be done. Lightening arrestors shall also be provided.
8. To provide all contract / casual / skilled semi-skilled labors during SUPERVISION of Installation & Commissioning of quoted systems.
9. All tools & tackles, welding equipment with skilled welder and consumables, lifting equipment such as jacks, cranes & forklifts, standard of weights for calibration shall be provided.
10. To honor the payment commitments as mentioned above and arrange for the remittance as per the terms agreed upon.
11. To arrange for all entry permits and also ensure safety for our engineers at site.

B. Our´s :

1. To conduct technical discussions with the authorized representatives and to freeze the technical specifications.
2. To take up the manufacture / supply of the items ordered as per the approved (Only in case of Non-Standard / Custom built equipment) specifications and drawings.
3. To intimate the Buyer when the product is ready for the inspection and approval prior to the dispatch (if required as per the purchase order). However it is understood that the cost of travel, stay etc of the inspector/s will be in the scope of the buyer.
4. Dispatch the goods to the locations after the inspection clearance for the dispatch is received, as per the instructions of buyer and present the dispatch documents as per the terms agreed up on.
5. Provide services for commissioning of the system as agreed and mentioned in your purchase order.

General Sales Terms And Conditions

Validity	:	30 days from date of quotation.
Price Basis	:	Ex-Works, Bangalore.
Delivery	:	8 Weeks for date of technically & commercially clear PO
P&F	:	Inclusive
Freight Charges	:	Extra at actuals
Octroi / Entry Tax	:	Extra At Actual, if Applicable
Transit Insurance	:	To **Your** Account.
Payment Terms	:	30% Along with Purchase Order; 70 % against PI before dispatch.
Excise Duty	:	Extra as applicable at the time of dispatch. Presently 12.5%
VAT	:	Extra as applicable at the time of dispatch. Presently 14 % or 2% Against Form "C"
Installation & Commissioning	:	Price as mentioned above
Warranty	:	The systems would be under warranty against manufacturing defects, for 18 Months from the date of dispatch or 12 months from the date of installation whichever is earlier.
Contract Review	:	Each party reserves the right of contract review if any changes are made to the terms of this offer. Any changes made in the terms, specifications, design, process requirements while awarding the contract against this offer needs to be discussed and accepted mutually before becoming binding on either party.

Minebea intec
The true measure

Purchase Order To : **M/s. Sartorius Mechatronics India Pvt. Ltd.**
Be Addressed To #26-D, Phase 2, KIADB Industrial Area,
Peenya, Bengaluru – 560058. India

For Sartorius Mechatronics India Pvt. Ltd,

Prashanth Gowda
Manager – Inspection Technology