NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Ferrero India Pvt Ltd
IMSOFER Division (Unit I) ,Plot No. F-13,
M.I.D.C., Baramati,
Maharashtra, India

Date : 23.02.2021
Quote NO : SQT.20.21.3051
Kind Attn : Mr Tausif Shaikh
Email Id : tousif.shaikh@ferrero.com
Contact No: 7722023571

Project Name & Location: Baramati

Subject : Quotation for Pit Mounted Scissor Lift

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size	Qty	Supply Charges in INR		Installation Charges in INR	
		Working Platform (in mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Pit Mounted Scissor Lift (2 Ton)**	(W) 1200 mm X (L) 1200 mm	1	230,000	230,000	15,000	15,000
			Total		**230,000**		**15,000**
	P&F Charges on Total Supply Value		3%		**6,900**		
	Total Without Taxes				**236,900**		**15,000**
	GST Extra @ 18%		18%		42,642		2,700
	Total With Taxes				**279,542**		**17,700**
	Transportation Charges				**In Client Scope**		
	Unloading Charges @ Site				**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) **Technical Specification -**

Pit Mounted Scissor Lift



Sr. No	Description	Specifications
1	**Capacity**	2 ton (2000 KG)
2	**Platform size**	(W) 1200 mm X (L) 1200 mm
3	**Shut ht**	250 mm
4	**Max ht**	750 mm
5	**Lift ht**	500 mm
6	**Power pack**	1HP 3Phase
7	**Safety**	Photocell
8	**Oil Tank**	SERVO 68 = 5 LTR
9	**Safety Railing on Two Side**	40 mm Height
10	**Control Panel**	1 HP STD
11	**Paint (RAL 1004)**	Golden Yellow
11	**Accessories**	Photocell , Proximity Sensors & Relay card

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 -9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Amol Gaware on 7758820333.**

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd