Sales Quotation

Quotation No - SQT/17-18/0067R1 **20-02-2018**

Duflon Industries Pvt Ltd
C-101, MIDC, Mahad
Dist Raigad 402309
Maharashtra

Kind Attn : Mr. Anil Mahadik
Email : mahadik@duflon.com
Contact No : 9422693180

Subject : Quotation for Manipulator & Conveyor System

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.

This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Qty	Unit	Rate In INR	Net Amount INR
	Manipulator : 1. Manipulator enables the safe and efficient handling of many products up to a maximum weight of 150 kg. 2. Manipulator incorporates a pneumatic cylinder to achieve the lifting action, and is normally custom built to suit the relevant working environment 3. Low noise levels and low maintenance make manipulator the ideal solution for your material handling problems 4. Three control styles ensure maximum flexibility. Auto balance, powered lift/lower, and pre-set loaded/unloaded options allow the most suitable control style to be used for each handling application.				
					
A	**Rail Mounted Manipulator**				
1	Manipulator Type : Pneumatic	**1**	**No.**	**8,30,000**	**8,30,000**
	Manipulator 6 Bar , Capacity : 150 kg				
	Maximum working Radius / Span : 3000 mm				
	Minimum Vertical Lift from Floor : 300 mm				
	Maximum Vertical Lift from Floor : 1400 mm				
	Air Booster with Tank	**1**	**No.**	**1,30,000**	**1,30,000**
	Hook for Lifting with pendulum				
	4 X 4 Roof Mounted Railing System	**1**	**No.**	**2,76,000**	**2,76,000**
	I Beam Structure	**1**	**No.**	**2,00,000**	**2,00,000**
	Installation charges for above Manipulator	**1**	**No.**	**20,000**	**20,000**
A	**Total**	**1**	**Set**		**14,56,000**
B	**Belt Conveyor**				
1	Motorised Roller Conveyor with Length 11 meter & width 500 mm	**2**	**Nos**	**11,38,000**	**11,38,000**
2	Motorised Roller Conveyor with Length 1800 mm & width 500 mm				
5	**Installation Charges For Roller Conveyor**	**1**	**No**	**30,000**	**30,000**
B	**Total**	**1**	**Set**		**11,68,000**

GST PUNE :	**27AAECN0437H1ZM**
HSN CODE :	**8428.90.90**

Amount In Words	**Total (A+B)**	**26,24,000**
	Rupees Twenty Six Lacs Twenty Four Thousand Only	

Technical Specifications For Roller Conveyor :

Sr No.	Describtion	Technical Specification
1	Conveyor type	Horizontal
2	Application of conveyor	Non Food
3	Sub type of conveyor	Roller
4	Material to be Convey on Conveyor	Dies
5	Weight of Conveying material	100 kg
6	Size of conveying material	400 mm
7	Speed of Conveyor (mtrs/min)	25 meter per minute
8	Roller to Roller Pitch	100 mm
9	Entire Load on conveyor	1200 kgs
10	Temperature	Room temp
11	Material of Construction	Powder coated MS Frame
12	Roller Material	SS 304
13	Total length of conveyor	23 meter
14	Width of conveyor	500 mm
15	Loading Height	400 mm
16	Delivery Height	800 mm
17	Power unit	With motor gearbox and VFD
18	Legs with	Articulated Foot pad
19	Paint For conveyor	Std Blue
20	Roller Type	Powered

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1. **Price** : Ex. Works Pune
2. **P & F Charges** : 3% Extra as applicable.
3. **Freight Notes** : Extra as applicable.
4. **Delivery** : 8-10 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5. **Payment** : 80% advance along with confirm Purchase Order & balance before dispatch
6. **Insurance** : Extra as applicable.
7. **GST** : Extra as Applicable on total supply value.
8. **Validity** : Validity of Offer is 15 days from the of quotation
9. **Warranty** : 12 Months from the date of supply

Please feel free to Contact **Mr. Mayur Derle** on **7709209333** For any further Clarification /Information in this Concern.

With Best Regards

Pooja Badre

7709586333

For Nihva Technologies Pvt Ltd