NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Hafele India Pvt Ltd
Office No. 3, Building A Beta,
I Think Techno Campus, Off J.V.L.R.,
Opp. Kanjurmarg Stn, Kanjurmarg-East, Mumbai- 400042

Project, Location : Pune

Date : 17.11.2020
Quote NO : SQT.20.21.2826
Kind Attn : Rahul Chavan
Email Id : Rahul.Chavan@hafeleindia.com
Contact No: 7045778237

Subject : Quotation for Access Control Terminals

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**F22 Access Control Terminal**	80.7 mm	19.4 mm	1	20,000	20,000	10,000	10,000
2	**uFace 401 / 402 Access Control Terminal**	165 mm	111 mm	1	29,000	29,000	10,000	10,000
3	**K40 SSR Fingerprint Time Attendance Terminal**	136 mm	37.6 mm	1	59,000	59,000	10,000	10,000
	Total			**3**		**108,000**		**30,000**
4	P&F Charges			3%		3,240		
	Total Without Taxes					111,240		30,000
	GST Extra @ 18%			18%		20,023.20		5,400
	Total With Taxes					**131,263**		**35,400**
5	Transportation Charges					Extra at atcual		
6	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

F22 Access Control Terminal

Sr .No.	Specification	F22 Access Control Terminal
1	**Display**	2.4 Inch TFT LCD Color Screen
2	**Fingerprint Capacity**	3000
3	**Card Capacity**	5000 (Optional) ID or mifare Card
4	**Transaction Capacity**	30000
5	**Sensor**	BioID Sensor/ SilkID Sensor (Optional)
6	**Communication**	RS232/485, TCP/IP, USB-host, Wi-Fi
7	**Access Control Interface**	3ed party electric lock, Door Sensor, Exit Button, Alarm
8	**Wiegand Signal**	Input , Output
9	**Aux. Input**	1ea for linkage function
10	**Function**	DST, Automatic Status Switch, Record query, T9 input, 14 digit user ID, Anti-Passback, Scheduled-Bell, Printer(Optional), ADMS(Optional)
11	**Power Supply**	12V DC, 3A
12	**Dimension**	159.8 X 80.7 X 19.4 mm

F22 Access Control Terminal

Sr .No.	Specification	F22 Access Control Terminal - 401
1	**Display**	4.3 Inch Touch Screen
2	**Face Capacity**	1200 (1:N) 3000 (1:1)
3	**ID Card Capacity**	10000
4	**Fingerprint Capacity**	/
5	**Logs Capacity**	100000
6	**Communication**	TCP/IP, USB Host, Wi-Fi (Optional)
7	**Standard Functions**	Automatic Status Switch, Self-Service Query, Work Code, SMS, DST, T9 input, 9 Digit User ID, Scheduled-Bell, Photo-ID
8	**Optional Functions**	Mifare Card, 3G, ADMS, 200mAh Back up Battery
9	**Power Supply**	12V 3A
10	**Dimension**	193.6 X 165 X 111 mm
11	**Package Weight (KG)**	1.84

Sr .No.	Specification	F22 Access Control Terminal - 402
1	**Display**	4.3 Inch Touch Screen
2	**Face Capacity**	1200 (1:N) 3000 (1:1)
3	**ID Card Capacity**	10000 (Optional)
4	**Fingerprint Capacity**	2000
5	**Logs Capacity**	100000
6	**Communication**	TCP/IP, USB Host, Wi-Fi (Optional)
7	**Standard Functions**	Automatic Status Switch, Self-Service Query, Work Code, SMS, DST, T9 input, 9 Digit User ID, Scheduled-Bell, Photo-ID
8	**Optional Functions**	Mifare Card, 3G, ADMS, 200mAh Back up Battery
9	**Power Supply**	12V 3A
10	**Dimension**	193.6 X 165 X 111 mm
11	**Package Weight (KG)**	1.87

K40 SSR Fingerprint Time Attendance Terminal

Sr .No.	Specification	K40 SSR Fingerprint Time Attendance Terminal
1	**Fingerprint Capacity**	1000 (2000 without SSR)
2	**ID Card Capacity**	1000 (Optional)
3	**Record Capacity**	80000
4	**Display**	2.8 Inch TFT Screen
5	**Communication**	TCP/IP, USB Host
6	**Standard Function**	Work Code, SMS, DST, Self-Service
		Query, Automatic Status Switch
		Scheduled-Bell, T9-Input, 9 Digit User ID,
		Build-in Battery, Simple Access Control or External Bell
7	**Optional Function**	ID or mifare Card
8	**Software**	Attendance
9	**Power Supply**	DC 12V 1.5A
10	**Verification Speed**	<=0.5 Sec
11	**Dimension**	184 X 136 X 37.6 (Length*Width*Height)

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order & Advance Payment.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Vijay Tarak on 8551093333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd