NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Patvin Engineering Private Limited
Patvin House, W-193, TTC Industrial Area,
MIDC Khairane, Navi Mumbai - 400 709

Project, Location : MSIL-Gurgaon

Date : 16.08.2021
Quote NO : SQT.20.21.2669R3
Kind Attn : Mr. Pranav Vaidya
Email Id : pranav_vaidya@patvin.co.in
Contact No: 8828198478

Subject : Revised Quotation for Fire rated Sliding Door at Maruti Suzuki Plant

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Double Leaf Type Door (Fire Rated 120 min)	1270	2100	1	65,000	65,000	Inclusive	
2	Single Leaf Type Door (Fire Rated 120 min)	970	2100	1	45,000	45,000	Inclusive	
3	Sliding Type Door (Fire Rated 120 min)	1700	2100	1	165,000	165,000	Inclusive	
	Total			**3**		**275,000**		**-**
4	P&F Charges			0%		-		
	Total Without Taxes					275,000		-
	GST Extra @ 18%			18%		49,500		-
	Total With Taxes					**324,500**		**-**
5	Transportation Charges					Extra at atcual		
6	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

2 Hrs Fire Rated Single / Double Leaf Doors

Sr .No.	Specification	2 Hrs Fire Rated Single / Double Leaf Doors
1	**Wall Opening(w)- mm**	970 mm & 1270 mm
2	**Wall Opening(H)- mm**	2100 mm
3	**Insulation**	Honeycomb/Rockwool
4	**Frame & Shutter Material**	GI
5	**Frame & Shutter Finish**	Powder Coating
6	**Vision Panel**	(200x300) 6 mm thick Glass for fire rated Door Scotch Pyran Make
7	**Panic Bar**	Single point panic device suit to door leaf of 1200mm width Geze Make(98536303)
8	**Trim Bar**	External Trim Bar(GEZE Make)
9	**Door Closure**	GEZE Overhead rack and pinion door closer GEZE TS 1000 C, EN 2/3 & 4 with adjustable closing speed and adjustable latching action,also available with mounting plate(1010001)
10	**Lock**	Mortise Sesh Lock with 70mm With Lever Handle

Fire Rated Sliding Door

Sr. No	Description	Specification
1	**Description**	BS 476 part(20 & 22)tested at CBRI :Central Building Research Institute, Roorkee
2	**Wall Opening(w)- mm**	1700 mm
3	**Wall Opening(H)- mm**	2100 mm
4	**Insulation**	Honeycomb/Rockwool
5	**Frame & Shutter Material**	GI
6	**Frame & Shutter Finish**	Powder Coating
7	**Fire rating**	120 Minute (2 Hours) for Integrity and stability.
8	**Accessories Included**	Fusible link, wire rope, guide rail, counter weight, pulleys as per BS 476, Part 20 & 22 and standard accessories included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune
Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment : 60% Advance along with Confirmed Purchase Order, 30% Balance before dispatch and 10% after Installation.
Validity : Validity of Offer is 15 days from the date of quotation
Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd