NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/18-19/0045R3 **Date : 28-11-2018**

INDAMAR AVIATION PVT LTD
Hanger no 1 , Juhu airport
Vile Parle (w) Mumbai 400056
Maharashtra, India

Kind Attn : Mr. Prashant Tidke
Email : Prashant@mahimtura.net
Contact No :

Project Name & Location : Indamar, Nagpur

Subject : Revised Offer for Sliding Gate & Swing Gate.

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Two Leaf Motorised Telescopic Bi Parting Sliding Gate with Painting (Supply + Installation)**				
1	**Size: (W) 35m X (H) 1.8m** • OUTER Frame –80X80X3.2mm • INNER TUBES - 40X40X2mm • Gap between tubes – 125 mm	1	No	2,675,000	2,675,000
2	Installation Charges for Above Gates	1	No	40,000	40,000
	Total				**2,715,000**
B	**Motorised Single Leaf Sliding Gate (Supply + Installation)**				
1	**Size: (W) 9 m X (H) 1.8m** • OUTER Frame –80X80X3.2mm • INNER TUBES - 40X40X2mm • Gap between tubes – 125 mm	1	No	500,000	500,000
2	Installation Charges for Above Gates	1	No	20,000	20,000
	Total				**520,000**
C	**Manual Doubel Leaf Swing Gate (Supply + Installation)**				
1	**Size: (W) 6 m X (H) 1.8m** • OUTER Frame –80X80X3.2mm • INNER TUBES - 40X40X2mm • Gap between tubes – 125 mm	2	No	320,000	640,000
2	Installation Charges for Above Gates	2	No	15,000	30,000
	Total				**670,000**
				Total value of Gates	**3,905,000**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Scaffolding require for Installation it is in client scope.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account
3. Billing will be as per the supply of material ,not as per site measurements

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex Works Pune
2	**P & F Charges**	:	NIL
3	**Freight Notes**	:	Extra As applicable
4	**Delivery**	:	7 -8 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST @18%
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Vijay Tarak on 8551093333** For any further Clarification /Information in this Concern.

With Best Regards

Varsha

8551091333

For Nihva Technologies Pvt Ltd