Sales Quotation

Quotation No - SQT/19-20/1690R1 **Date : 04-07-2019**

ABB Robotics
Bangalore
Karnattaka

Kind Attn: **Mr. Mithun Pawar**
Email: mithun.pawar@in.abb.com
Contact No: 91 97400-58173

Project Name And Location :

Subject : Quotation for Machine Protection Door RP300
Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Albany Make Rapid Roll Up Door RP300**				
Door version:	Vertical Rapid Roller Door for machine protection.				
Side Frames:	Aluminum anodized two parts, to have easy access to switches and service.				
Door blade:	PVC material transparent with reinforcement stripes silicone-free in blue (similar RAL 5010).				
Bottom beam	Aluminium anodized.				
Drive unit:	Drive unit IP 55, either RH or LH as an option, with control cable (standard length = height of door)				
Opening / closing speed:	Approx. max. 2,3 / 1,3 m/s				
Control system:	MCC Vector Control				
Power suppy:	3/(N)/PE 230/380/400/415 V, 50 Hz				
Safety features:	Safety edge with cable chain integrated in side frames, door line photocell (Transmitter / Receiver) inside side frames, emergency crank and mechanical drop-down protection.				
Safety limit switch:	1 Schmersal safety limit switch PL e EN ISO 13849-1, SIL 3 EN 62061 on drive side integrated in the side frame to save space.				
1	**Size:(W) 2000 mm x (H) 2500 mm**	2	No	598,500	**1,197,000**
2	**Size:(W) 4000 mm x (H) 2500 mm**	3	No	670,000	**2,010,000**
				Total	3,207,000

GST Pune	27AAECN0437H1ZM
HSN High Speed Door:	73083000

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	FOR @ Site
2	**P & F Charges**	:	nil
3	**Freight Notes**	:	Inclusive
4	**Delivery**	:	9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	15 Days immediate against delivery
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST Extra @18%
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 0855109633** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd