NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company
GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Client Name - **Mr Vishal Shukla**

Date : 23.03.2026
Quote NO : RR 25.26.0182
Kind Attn : Mr Vishal Shukla
Email Id : vishalshukla0204@gmail.com
Contact No: 8180004806

Project Name & Location: Holiday Inn, Ujjain

Subject : Commercial Offer for Window with Glass Tostem Brand

Dear Sir / Ma'am,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer for Windows without Mullion	1
B.	Commercial Offer for Windows with Mullion	1
C.	Technical Specification	2
D.	General Conditions	2
E.	Terms & Condtions	2

A) **Commercial Offer for Windows without Mullion**

Sr no	Description	Size (mtr)	Design	Qty (Nos)	Supply Charges in INR	
					Unit Rate	Total
1	**Glass Window (with Mullion)**	• 2000 W X 2250 L • Fixed • Installation Inclusive		141	₹ 75,714	**₹ 1,06,75,674**
2	**Glazing bead 5,8,13.52,24 mm. (5m)**			30	₹ 12,857	**₹ 3,85,710**
3	**PUSH BOTTON (1PCS/PACK)**			62	₹ 450	**₹ 27,900**
4	**SCREW SET FOR FITTING FRAME(100 PCS/ BOX**			62	₹ 1,900	**₹ 1,17,800**
5	Sub-total					**₹ 1,12,07,084**
6	Installation Charges					**Extra 25000/- per item**
7	GST Extra @ 18%			18%		**Extra At Actual**
8	P&F Charges @ 3%			3%		**Extra At Actual**
9	Transportation Charges					**In Client Scope**
10	Unloading Charges @ Site					**In Client Scope**
11	Lifting Equipment required @ desired floor					**In Client Scope**
12	Support Structure if required @ site					**In Client Scope**

B) **Commercial Offer for Windows with Mullion**

Sr no	Description	Size (mtr)	Design	Qty (Nos)	Supply Charges in INR	
					Unit Rate	Total
1	**Glass Window (with Mullion)**	• 2000 W X 2250 L • Fixed • Installation Inclusive		141	₹ 70,031	**₹ 98,74,371**
2	**Glazing bead 5,8,13.52,24 mm. (5m)**			44	₹ 5,679	**₹ 2,49,876**
3	**PUSH BOTTON (1PCS/PACK)**			79	₹ 426	**₹ 33,654**
4	**SCREW SET FOR FITTING FRAME(100 PCS/ BOX**			79	₹ 1,794	**₹ 1,41,726**
5	Sub-total					**₹ 1,02,99,627**
6	Installation Charges					**Extra 25000/- per item**
7	GST Extra @ 18%			18%		**Extra At Actual**
8	P&F Charges @ 3%			3%		**Extra At Actual**
9	Transportation Charges					**In Client Scope**
10	Unloading Charges @ Site					**In Client Scope**
11	Lifting Equipment required @ desired floor					**In Client Scope**
12	Support Structure if required @ site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company
GST Pune : 27AAECN0437H1ZM

C) **Technical Specification**

Window without Mullion	Windows with Mullion
Grants	**Atis**
Track width-120 mm & Track Height - 60mm	Track width-88 mm & Track Height - 55mm
Windows are tested for - a) Wind Pressure - 2000 pa b) Water tightness - 300 pa c) Air tightness - 10.7 m cube / h.m. square d) Noise insulation- 25-30 DB within single Tgh Glass	Windows are tested for - a) Wind Pressure - 1600 pa b) Water tightness - 250 pa c) Air tightness - 10.7 m cube / h.m. square d) Noise insulation- 25-30 DB within single Tgh Glass
System Aluminium windows - T5 6063 Alloy used	System Aluminium windows - T5 6063 Alloy used
System is vertically Anodised with patented Textguard technology provides color defadeness warranty upto 40 years	System is vertically Anodised with patented Textguard technology provides color defadeness warranty upto 40 years
Scratch resistance upto 5 H, Dust repellant	Scratch resistance upto 5 H, Dust repellant
System is covered with EPDM Gasket Having 20 years of warranty helps in sound insulation & water tightness	System is covered with EPDM Gasket Having 20 years of warranty helps in sound insulation & water tightness
Glass thickness - upto 31.5 mm (depends on size of the aperture for sustaining Wind load & dead load)	Glass thickness - upto 24 mm (depends on size of the aperture for sustaining Wind load & dead load)
System is tested as per Japanese & American Std	System is tested as per Japanese & American Std

D) **General Conditions**

1. Continuous uninterrupted access to installation section or as agreed seperately.
2. Provision of 230 V power supply for hand tools.
3. A dry and secure area, not in direct sunlight is to be provided for storage of product component
4. Access to site between 7 am to 8 pm should be provided.
5. Any storage costs for material due to delay outside of NIHVA, will be in client scope.
6. The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practice. We reserve the right to extend the period accordingly.
7. Installation will start after receiving of Site Readiness Photographs or written Email communication.
8. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation.
9. For any reason if we need to stop our installation and demobilize the team without completing the work, then extra cost will be applicable for Remobilizing the Team.
10. If any change in dimension on actual site, quoted price will affect accordingly which will be in client scope.
11. After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost.

Note: **Please find below List which are in Client Scope**

Sr. No		Remark
1	Secured and fully covered Store area to keep the material.	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site.	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required.	In Client Scope
5	All structure support required.	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material, the additional quantities and wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

E) **Terms & Conditions**

Price :	Ex Works Pune.
Delivery :	4 - 6 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing Approval.
Payment :	80% Advance along with Confirmed Purchase Order. 10% After material Delivery at site. 10% After Installation.
Validity :	Validity of offer is 15 days from the date of quotation.
Warranty :	12 months from the date of supply. It only covers damage caused due to mechanical system not due to natural calamity.
Design Clause :	NIHVA shall be deemed the authors of their respective concept and drawings with reserved rights, including copyrights. It shall not be used by the owner for future additions or alterations to this Project or for another project or should not copied at any other future project or should not transfer or copied by anyone.
Compensation Clause :	Please note that in the event the buyer cancels an order, after the order is confirmed to us, it is binding to the buyer to pay NIHVA a compensation of 25% of order value.

With Best Regards

Pallavi Shirke

7410169333
NIHVA Technologies Pvt Ltd