FDAPL

Item No.	Description	Unit	Qty.	Rate	Amount Rs.
I	**CIVIL FINISHES WORK**				
I.9	Providing and fixing NIHVA Make Automatic sliding Retractable roof with European make electric drive inbuilt control, safety sensor, temperature sensor, electromagnetic limit switch with Aluminum Structure and frame with pure polyster powder of thickness 75-80 microns and Polycarbonate sheet of Polycarbonate Compact Clear / Embossed 4.0 mm Thick with central opening. The power supply 450W 230V & 50/60hz. The minimum speed of operation should be 0.28m/s with a driving force of 900N. The minimum working temp should be- 20 degree and maximum working temperature should be 50 degrees. The dimension of motor should be approximately 330x210x303 mm with an utmost weight of 13kg. The control unit should be pull out unit protected by casing and buffer batteries. The synchronisation should be Master/slave system with control system with pendant and remote controlled. The minimum programming level can be 8. There should be option of home automation connectivity. It should come with optional and mandatory feature like receiver, transmitter, photocell and flashing light. The glazing tensile stress and strength should be more than 60 MPa with maximum 6% elongation. The glazing dielectric strength should be 35 kV/mm as per IEC 60243-1. The Vicat softening temperature should be 148-degree Celsius as per ISO 306. The heat deflection temperature under load of 1.80 MPa is 127-degree Celsius with minimum impact strength of 11 kJ/mm. The structural material Grade of AL should be AL 6060-T4, AL 6060- T6. The Aluminium profile should be Specially extruded Non corrosive AL hollow profile with material composition of AL (%) > 98% Si (%) = 0.30 (min) – 0.70 (max). The dimensional tolerance should not be more than ± 20mm and the angularity tolerance should not be more than ± 1%. Rate should be inclusive of Annodized AL Guide , Interlocking system with 4 motor mechanism a. 2 remote controlled, Single phase bidirectional motor, Speed 9-12 m / Min, Power as per requirement, mechanical limit switch, EPDM Gaskets and sealnats, SS Fastners, Polycarbonate sheets shall be with UV Protection layers and 'U' values as per energy saving norms , ensuring water tightness by applying silicon sealant in gaps ensuring 100% water tightness, Virgin PVC ,gaskets of approved make / manufacturer for roofing over open courtyard . Rate should be should be quoted for at all levels , all height including the necessary scaffolding, curing, cleaning of floor from Mortar dropouts etc complete. to the satisfaction of Engineer-in-charge. Work should be as per detail design & drawing and satisfactory of the Architects. Rate should be inclusive of required structural steel frame work and all required structural steel work painted with synthetic enamel paint (two coats) with primer and required double legged independent scaffolding for entire height or as required to approval of the PM.	sq.m	529.20		