	IPS-MEHTALIA PVT. LTD. Consulting Engineers • Construction Management • Commissioning & Qualification B101-109, Kailash Vaibhav Ind. Complex, Vikhroli (W), Mumbai – 400 079		**Client**	Perstorp
			Project No.	MBD18019
			Made / App	SNS /KVV
	Document Title	Dock Leveller	**Rev**	R 2
	Document No.	IPS-MBD18019-ME-389-40KTPA-DE	**Date**	25-Jun-19

Annexure-1 Dock Leveller

Sr. No.	Description	IPS- Mehtalia Specification	Vendor to Specify
	General		
	Title	Dock Leveler (Hydraulic operated)	Dock Leveler (Hydraulic operated)
	Quantity	4.0	4 Nos
	Location	Outside	Outside
	Capacity (Tons)	6.5	6.5 Tons
	Service	For loading / unloading of palates from LCV / HCV	For loading / unloading of palates from LCV / HCV
	Type of installation	Pit type	Pit type
	Platform height from road level (m)	1.2	1.2 mtr
	Size	Suitable for heavy container	2000X2500X480
	Design standard	EN 1398	EN 1398
	Finishing/Painting	2 coats of Zinc chromate primer with 2 coats of synthetic black enamel. Paint shall be applied after cleaning surface with wire brush / cloth to remove dust and oil	2 coats of Zinc chromate primer with 2 coats of synthetic black enamel. Paint shall be applied after cleaning surface with wire brush / cloth to remove dust and oil
	Type	Hydraulic operated	Hydraulic operated
	Capacity	VTS	6.5 Tons
	Max. Travel (up / down) mm	VTS	300/200
	Travel Speed (M/sec) mm	VTS	
	Dimensional details	VTS	(W) 2000 mm X (L) 2500 mm
	Platform size (l x w) m	VTS	(W) 2000 mm X (L) 2500 mm
	Lip size (l x w) m	VTS	(W) 2000 mm X (L) 2500 mm
	Working length	VTS	2900 mm
	Overall length	VTS	2000 X 2900
	Maximum slope	0.08	10%
	Pit size required (l x w x h)M	VTS	2550 X 2050 X 485
	Hydraulic power pack details		1 HP, 3 PH
	Make	VTS	Imported
	Overall dimensions (l x w x d)m	VTS	(W) 2000 mm X (L) 2500 mm X (H) 400
	Operating oil pressure	VTS	180 kg/cm2
	Max. Oil pressure	VTS	180 kg/cm2
	Safety valve set pressure	VTS	120kg/cm2
	Drive details		Direct by Electric Motor
	Type	Sq. cage induction type, high efficiency (EFF-1) motor	
	Transmission type	Direct	
	Enclosure	TEFC, IP 55, with class F insulation	
	Total power consumption (Kw)	*	0.75kW
	Power supply	415 (±10%)V ; 50(±5%)Hz; 3 phase	415 (±10%)V ; 50(±5%)Hz; 3 phase
	Motor rating (Kw / poles)	VTS	0.75kW
	Other details		
	Oil grade	VTS	Servo 68
	Oil charge	VTS	
	Oil life	VTS	As per Pressure
	Material of Construction		As per use
	Platform	VTS	As per use/ ms
	Lip and bridge deck	VTS	Ms
	Supporting structure	VTS	Ms

*** VTS- Vendor to specify**