NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Volumnus Developers Pvt Ltd
Greenbase Industrial & Logistics Park
Hiranandani Park, Thriveni Academy, Vadakkupattu - Post,
Kanchipuram District, Chennai - 603204

Date : 01.4.2021
Quote NO : SQT.20.21.2957R3
Kind Attn : P.Murugan
Email Id : pmurugan@hrealty.com
Contact No: 9360330236

Project, Location : Hiranandani, Chennai

Subject : Revised Quotation for Rolling Shutter, Dock Leveler and Fold Up Doors

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Motorized Rolling Shutter**	4000	5000	1	191,000	191,000		-
2	**Motorized Rolling Shutter**	4000	4000	3	171,000	513,000		-
3	**Motorized Rolling Shutter**	3000	2450	1	125,000	125,000		-
4	**Motorized Rolling Shutter**	2450	3000	6	132,000	792,000		-
5	**Motorized Rolling Shutter**	2450	3000	9	118,000	1,062,000		-
6	**Fold-Up Doors**	10000	10000	4	2,634,000	10,536,000		-
7	**Dock Leveler with Split-Lip individual Hydraulic opereated Dock leveler with customised Powerpack & Customised Control panel, Powder-Coating. 6Ton**	2000	3000	5	450,000	2,250,000		-
	Total			**29**		**15,469,000**		**-**
8	P&F Charges			3%		464,070		
	Total Without Taxes					15,933,070		-
	GST Extra @ 18%			18%		2,867,952.60		-
	Total With Taxes					**18,801,023**		**-**
9	Transportation Charges					In NIHVA Scope		
10	Unloading Charges @ Site					In NIHVA Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Rolling Shutter

Sr .No.	Specification	GI Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with GI Slats with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick GI.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick.
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm
12	**Surface finish**	PU paint or Powder coated
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection



Fold Up Door

Sr. No.	Description	Specification
1	Product	High Speed Door-Fold up type (All Imported Components)
2	Opening Direction	Vertical
3	Mounting Location	Inside of the bay, inside the building
4	Opening/Closing Speed	0.5m/Sec. -1.0m/Sec.
5	Wind Resistance	90km/h – 110 km/h
6	Curtain Material	Curtain is in PVC made by anti-tear polyester fabric
7	Curtain Weight	680 gr/sqm
8	Tensile Strength Warp/Weft (N/5Cm)	DIN 53354 - DIN EN ISO 1421/met. 1 – 2500/2500 N/50 mm
9	Stiffeners	Polycorbinate pipes
10	Tear Strength	Warp/Weft DIN 53363 – 250/250 N
11	Temperature range	-30°C +70°C
12	Flame Resistance	reaction in class 1 or 2
13	Vision Panel	One row of transparent PVC windows, in rectangular size, assures a good visibility
14	Fabric Color	Standard Blue, Grey, Red, Optional with various colors
15	Fold Up Arrangement	Segmented PVC curtain is folded up through lifting belt & tube mechanism
16	Roller Shaft	Tubular pipes with lifting belts
17	Side Guide Rails	Self supporting Galvanized steel structure
18	Bottom Profile	PVC profile
18	Side Brackets	Galvanized steel brackets with bearings

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Dock Leveler

Sr .No.	Specification	Specifications
1	**Capacity**	6 Ton
2	**Platform Size**	2000 W X 3000 L
3	**Dock Height**	480 mm
4	**Deck Lift above**	300 mm
5	**Deck Lift below**	250 mm
6	**Height of Dock from road Level**	1200 mm
7	**Power Pack Costomised**	1HP, 3 Phase
8	**Control Panel(4 UP & 4 DOWN)**	1 HP
9	**Hydraulic Cylinders Deck 2 & Lip 2**	Approx bore 50 mm
10	**Hydraulic Oil**	Servo 68 = 15 Ltr
11	**Paint (RAL 1004) Power Coating**	Golden Yellow

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In NIHVA Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks for Rolling Shutter, 10-12 weeks for Fold Up Doors and 8-9 weeks for Dock leveler from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Bhavin Jain on 8551092333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd