NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Conglomerate
off no 13,bldg. no A,Zambharae Heritage ,
Chavhan Nagar,Dhankawadi Pune 411043

Project, Location : Pune

Date : 31.10.2020
Quote NO : SQT.20.21.2794
Kind Attn : Harish Pitambar Chahan
Email Id : conglomerate.pune@gmail.com
Contact No: 9881032643

Subject : Quotation for Pit Mounted Electro Hydraulic Scissor Lift

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Pit Mounted Electro Hydraulic Scissor Lift**	2500 (W)	3500 (L)	1	617,000	617,000	15,000	15,000
2	**High Speed Roll up Door**	4000	5000	1	392,000	392,000	20,000	20,000
	Total			**2**		**1,009,000**		**35,000**
3	P&F Charges			3%		30,270		
	Total Without Taxes					1,039,270		35,000
	GST Extra @ 18%			18%		187,068.60		6,300
	Total With Taxes					**1,226,339**		**41,300**
4	Transportation Charges					Extra at atcual		
5	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Electro Hydraulic Mobile Scissor Lift

Sr. No	Description	Specifications
1	**Capacity**	5000 KG
2	**Platform size**	3500 mm(L) X 2500 (W) mm
3	**Shut ht**	700 mm
4	**Max ht**	2300 mm
5	**Lift ht**	1600 mm
6	**Power pack**	5 HP, 3 Phase
7	**Oil Tank**	50 Ltr
8	**Control Panel**	5HP STD
9	**Hydraulic Cylinder**	APPROX BORE 100 mm
10	**Color (RAL 1004)**	GOLDEN YELLOW

High Speed Roll up Door

Sr. No	Description	Specifications
1	**Use**	Internal / External
2	**Curtain**	Aluminium 19.0mm
3	**Opening Speed**	1,0 m/s
4	**Closing Speed**	0,7 m/s
5	**Resistance to Wind Load**	EN 12424 Class 3
6	**Door Leaf Material**	Polyurethane filled RAL 9006 aluminium lamella
7	**Security Features**	EN 13241 - 1
8	**Guide Material**	Aluminium Anodized
9	**Operator and Control**	Connecting Voltage 1-phase 220V - 1ph, N
		3-phase 380V - 3ph, N
		Open-Stop-Close Button
		Emergency - OFF Button
10	**Emergency Opening**	Crank Handle

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAFCN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mrs. Sneha Bharane on 8551035333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd