NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

PSP Projects Ltd.
PSP House, Opp. Celesta Courtyard, Opp. Lane of Vikramnagar Colony,
ISCON-Ambli Road, Ahmedabad – 380058.

Date : 05.09.2019
Quote NO : SQT.19.20.2020
Kind Attn : Mr. JAIMIN PATEL
Email Id : tender1@pspprojects.com
Contact No: **9067007001**

Project Name & Location: ASTRAL POLYTECHNIK LIMITED, Dholka

Subject : Quotation for Rolling Shutter & Sliding Glass Door.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	GI Rolling Shutter Motorised	5000	5500	1	382,000	382,000	20,000	20,000
2	GI Rolling Shutter Motorised	3000	4500	1	240,000	240,000	20,000	20,000
3	GI Rolling Shutter Motorised	4000	4500	1	262,000	262,000	20,000	20,000
4	Automatic Sliding Glass Door	1800	2400	1	283,000	283,000	20,000	20,000
			Total			**1,167,000**		**80,000**
5	P&F Charges			3%		**35,010**		
	Total Without Taxes					**1,202,010**		**80,000**
	GST Extra @ 18%			18%		216,362		14,400
	Total With Taxes					**1,418,372**		**94,400**
6	Transportation Charges					**In Client Scope**		
7	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sliding Glass Door	
ASSA ABLOY-BESAM-Automatic Sliding Door SL 500	
100% imported from Sweden	
Specifications :	
1. Main power supply	
2. Operator type- Bi part operator.	
3.Glass : 10mm thick toughened glass	

GI Motorised Rolling Shutter	
Door type	**Motorized Rolling Sutter**
Clear Opening dimension (w) -- x (h) --	(W) 5000 mm x (H) 5500 mm Qty - 1 (W) 3000 mm x (H) 4500 mm Qty - 1 (W) 4000 mm X (H) 4500 mm Qty - 1
Opening Direction	Vertical - from bottom to Top
Mounting Location area	Inside area / Outside area
Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side Guides: Not required for height below 3000mm
Curtain material	GI
Curtain Panel	The panel made of 1.0mm
Curtain panel size	75mm wide
Curtain Profile	Corrugation
Slat Thickness	0.9 mm to 1.2 mm (As per IS 6248)
Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension
Hood Cover	Made of GI Sheet Thickness 0.8 mm with 25x25x3mm angle stiffener
Surface finish	
Painting	2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer
Options Available	Perforation in Slat Profile
Automation	
Emergency Operation	Manual Hand Driven
Operating Switch	Push Button from inside

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333**

With Best Regards
Vivek
8530370333
For NIHVA Technologies Pvt Ltd