NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/17-18/0018 **Date : 10-06-2017**

PACKIT
6th Floor,Bellaire Tower
Gurgaon -122002

Kind Attn : Mr.Ankit Jain
Email : info@packit.co.in
Contact No : 9999948617

Subject : Quotation for Telescopic Conveyor

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best

Commercial Offer

Description	Qty	Unit	Rate In INR	Net Amount INR
Telescopic Conveyor (Make- Nihva)				
Specifications :-				
1.Capacity: 50kg/m **2.Belt width : 600mm** **3.Total length: 18.6 mtrs** **4.Extended: 12.6 mtrs** **5.Collapsed: 6 mtrs** **6.Type of load : Cartons & Hdpe Sacks** **7.Movement : Unidirectional with VFD feasibility**	**2**	**Nos**	**2165000**	**43,30,000.00**

VAT TIN :	27545250455 V
CST TIN :	27545250455 C
Service Tax No	AAECN0437HSD001
GST ID:	27AAECN0437H1ZM

Amount in Words	**Total Amount**	**43,30,000.00**
	Rupees Fourty Three Lacs Thirty Thousands Only	

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	3% Extra
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	10-11 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing
5	**Payment**	:	**80% advance along with confirm Purchase Order & balance before dispatch**
6	**Insurance**	:	Extra if applicable
7	**Sales Tax**	:	Extra as applicable at the time of dispatch. Presently @13.5% VAT (supply within Maharshtra OR @2% CST against Form C (Outside Maharashtra)& GST If applicable.
8	**Validity**	:	Validity of Offer is 15 days from the of quotation
9	**Warranty**	:	12 Months from the date of supply

Please feel free to Contact **Mr. Mayur Derle** on **7709209333** For any further Clarification /Information in this Concern.

With Best Regards

Pooja Badre

7709586333

For Nihva Technologies Pvt Ltd