NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Pharmadeep TURNKEY Consultants & Engineers Pvt Ltd.
B 509, Lodha Supremus II, Road No 22
Waghale Estate, Thane (West) 400604

Date : 10.06.2020
Quote NO : SQT/19-20/2555
Kind Attn : Mr. Kundan Chougule
Email Id : kundan@pharmadeep.com
Contact No: 9372767098

Subject : Quotation for ASSA ABLOY Make Clean room High Speed Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Location : Zone 1 (White Area)** **High Speed Door RRClean** **• Interlocking System With Fire Emergency arrangement** **• SS Supporting Frame**	1500	2100	6	6,26,000	37,56,000	20,000	1,20,000
2	**Location : Zone 2 (Colour Area, 10Kg)** **High Speed Door RRClean** **• Interlocking System With Fire Emergency arrangement** **• SS Supporting Frame**	1500	2100	2	6,26,000	12,52,000	20,000	40,000
3	**Location : Zone 3 (Colour Area, 25Kg)** **High Speed Door RRClean** **• Interlocking System With Fire Emergency arrangement** **• SS Supporting Frame**	1500	2100	2	6,26,000	12,52,000	20,000	40,000
4	**Location : Zone 4 (Colour Area, 50Kg)** **High Speed Door RRClean** **• Interlocking System With Fire Emergency arrangement** **• SS Supporting Frame**	1500	2100	2	6,26,000	12,52,000	20,000	40,000
5	**Location : Zone 5 (Colour Area)** **High Speed Door RRClean** **• Interlocking System With Fire Emergency arrangement** **• SS Supporting Frame**	1500	2100	8	6,26,000	50,08,000	20,000	1,60,000
6	**Location : Corridor** **High Speed Door RRClean** **• Interlocking System With Fire Emergency arrangement** **• SS Supporting Frame**	1500	2100	4	6,26,000	25,04,000	20,000	80,000
7	**Location : GROUND FLOOR FINISHED GOODS STORE** **High Speed Door RRClean** **• Interlocking System With Fire Emergency arrangement** **• SS Supporting Frame**	1500	2100	3	6,26,000	18,78,000	20,000	60,000
8	**Location : First Floor Store** **High Speed Door RRClean** **• Interlocking System With Fire Emergency arrangement** **• SS Supporting Frame**	1500	2100	4	6,26,000	25,04,000	20,000	80,000
9	**Location : First Floor-Process Area** **High Speed Door RRClean** **• Interlocking System With Fire Emergency arrangement** **• SS Supporting Frame**	1500	2100	5	6,26,000	31,30,000	20,000	1,00,000
10	**Location : GOODS LIFT-1** **High Speed Door RRClean** **• Interlocking System With Fire Emergency arrangement** **• SS Supporting Frame**	2500	2100	1	6,59,000	6,59,000	20,000	20,000
11	**Location : GOODS LIFT-2** **High Speed Door RRClean** **• Interlocking System With Fire Emergency arrangement** **• SS Supporting Frame**	1500	2100	1	6,26,000	6,26,000	20,000	20,000
			Total	**38**		**2,38,21,000**		**7,60,000**
12			P&F Charges	3%		7,14,630		
			Total Without Taxes			2,45,35,630		7,60,000
			GST Extra @ 18%	18%		44,16,413		1,36,800
			Total With Taxes			**2,89,52,043**		**8,96,800**
13			Transportation Charges			Extra At Actual		
14			Unloading Charges @ Site			Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

ASSA ABLOY Make Clean Room High Speed Door (100% Imported from Germany)

- Cleanroom suitability certified by Fraunhofer Institute
- Fulfils international standards and guidelines for cleanroom applications in accordance with DIN EN ISO 14644-1 and GMP
- ISO Class 5, GMP Class C
- Low particle emission
- Low air exchange thanks to fast opening and closing speed







Sr. No	Description	Details
1	Size	(W) 1500 mm X (H) 2100 mm - 37 Nos
2	Size	(W) 2500 mm X (H) 2100 mm - 01 No
3	Total Qty	38 Numbers
4	Description :	Certified flexible high performance door, opening in vertical direction, certified for the use in cleanrooms. Compliant to the national norms and regulations in cleanroom applications according to DIN EN ISO 14644-1 and GMP Certified according to ISO 5 and GMP class C. Low Particle emission , Low Air Exchange. Certified by Fraunhofer.
5	Door Curtain	Made of PVC with vertical reinforcement stripes in white (similar RAL 9016).
6	Self-supporting side frames made of stainless steel :	Self-supporting side frames max. DW 110 mm, motor cover , top roll cover & bottom profile are in Stainless Steel V2A
7	Lintel space requirement	410mm Minimum
8	Drive unit	Direct Drive Gear motor, mountable left or right
9	Supply voltage	3L/(N)PE 380/400/415/440/480V; 50/60 Hz
10	Control system:	• MCC Vector Control - frequency converter control system for a dynamic, smooth door movement, located close to the drive unit Max. Opening Speed 2.1m/s Max. Closing Speed 1.0 m/s • Graphic display and foil keypad for easy operation installed on the drive side.
11	Safety features:	Pre-running photocell, door line photocell integrated in the side frames, drop down protection in the drive unit

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410139333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd