**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**Address**
Delhi

**Date : 30.12.2019**
Quote NO : SQT.19.20.2317
**Kind Attn : Mr. Khanna**
Email Id : titensile@gmail.com
Contact No: 9990789996

**Project Name & Location: Centre Opening Roof-Temple Courtyard**

**Subject : Quotation for Centre Opening Roof**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 1 |
| C. | General Conditions | 2 |
| D. | Terms & Condtions | 2 |

**A) Commercial Offer**

| Sr No | Description | Size | Qty | Supply and Installation Charges in INR | |
|---|---|---|---|---|---|
| | | | (Nos) | Unit Price | Total Amount |
| 1 | Retractable Roof(Center Opening) | (W)17000mm x (L)21000mm x(H)2500mm- 6 Segment (Automatic) | 1 | 84,00,000 | 84,00,000 |
| | | | **Total** | | **84,00,000** |
| | | **Total Without Taxes** | | | **84,00,000** |
| | | GST Extra @ 18% | 18% | | 15,12,000 |
| | | **Total With Taxes** | | | **99,12,000** |
| 2 | | Transportation Charges | | | **In Client Scope** |
| 3 | | Unloading Charges @ Site | | | **In Client Scope** |

**B) Technical Specification -**

| |
|---|
| **1. Polycarbonate Korean or Israel Make compact clear/Embossed 4.0 mm Thick** |
| **2. Profile : Powder Coated AL Frame (As per RAL colour )** |
| **3. Guide : Annodized AL Guide** |
| **4. Interlocking** |
| **5. Motors with Remote Control**<br>**a) Single Phase Bi-directional Motor**<br>**b) Speed- 09-12m/min**<br>**c) Power- As per Roof Dimension**<br>**d) Mechanical Limit Switch**<br>**e) Rack and Pinion Arrangement -Z16/Molude4/Module6**<br>**f) Italian Make BFT Brand** |
| **6. Control Panel** |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1. Installation will start after receiving of Site Readiness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipments are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 5 to 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply , 10 years warranty for polycarbonate sheets and 5 years on powder coated AL Profile.

With Best Regards
Yogita
8530872333
For NIHVA Technologies Pvt Ltd