NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Bajaj Steel Industries Limited
Plot No. G-108 MIDC Industrial Area Butibori District Nagpur

Date : 30.10.2020
Quote NO : SQT.20.21.2775R1
Kind Attn : Shakeel Ahmad Qureshi
Email Id : saq@bajajngp.com
Contact No: 7219358594

Subject : Quotation for Telescopic Sliding Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	TELESCOPIC SLIDING GATE	14000	1800	1	650,000	650,000	20,000	20,000
				Total		**650,000**		**20,000**
2	P&F Charges			3%		19,500		
	Total Without Taxes					669,500		20,000
	GST Extra @ 18%			18%		120,510.00		3,600
	Total With Taxes					**790,010**		**23,600**
3	Transportation Charges					In Client Scope		
4	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Sliding Gate

Sr .No.	Specification	Telescopic Sliding Gate
1	**Door type**	Motorised Three Leaf Telescopic Sliding Gate
2	**Clear Opening gate dimension**	(W) 14000 mm X (H) 1800 mm
3	**Master Leaf Size**	5870 X 1675 mm
4	**1 ST Leaf Size**	5470 X 1675 mm
5	**2 ND Leaf Size**	5470 X 1675 mm
6	**Opening Direction**	Horizontal - from left to right or reverse
7	**Mounting Location area**	Inside area
8	**Design Pattern**	Standard Tubular Design Pattern
9	**Outer Frame Tube Sizes**	72 x 72 x 3.2mm MS SQ. TUBE
10	**Internal Vertical Tube Sizes**	25x25x3.20mm MS SQ. TUBE
11	**For Post**	72 x 72 x 3.2mm MS SQ. TUBE
12	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
13	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings
14	**Guide Rollers supporter during Gate movement**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
15	**Painting**	Two Coats of Primer and Two Coats of Synthetic Enamel Paint
16	**Control Panel**	2 Nos Operating Station.(Motor Panel and Security Room)
17	**Operation**	By Telescopic Mechanism
18	**Accessories**	1. Limit Switch for Cut out when Gate is fully Closed
		2. Flashing Light
		3. Remote
		4. Hooter
		5. Photocell

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6-7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Sneha Bharane on 8551035333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd