NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Garware Polyester Ltd
Waluj, Maharashtra

Date : 27.01.2020
Quote NO : SQT.19.20.2379
Kind Attn : Mr.Mayur Jadhav
Email Id : mayur.jadhav@garwarepoly.com
Contact No: 9376710357

Subject : Quotation for Sliding Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Motorised Two Leaf Sliding Gate	14500	1725	1	9,62,000	9,62,000	20,000	20,000
2	Motorised Two Leaf Sliding Gate	13750	1725	1	9,54,000	9,54,000	20,000	20,000
				Total Value		**19,16,000**		**40,000**
3			**P&F Charges**	3%		57,480		
				Total Without Taxes		**19,73,480**		**40,000**
				GST Extra @ 18%	18%	3,55,226		7,200
				Total With Taxes		**23,28,706**		**47,200**
4				Transportation Charges		**In Client Scope**		
5				Unloading Charges @ Site		**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Technical Specifications

Sr. No	Description	Specifications
1	Door type	Motorised Sliding Gate
2	Clear Opening gate dimension	(W) 14500 mm X (H) 1725 mm (W) 13750 mm X (H) 1725 mm
3	Opening Direction	Horizontal - from left to right or reverse
4	Mounting Location area	Inside area
5	Design Pattern	Standard Tubular Design Pattern
6	Outer Frame Tube Sizes	125 X 125 X 4.5 mm
7	Internal Vertical Tube Sizes	25 X 25 X 2.6 mm
8	For Post	80 X 80 X 4 mm
9	Gap Between Tubes	338 mm
10	Wodden Block sizes	650mm X 700mm on Front Side of Gate
11	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
12	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
13	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
14	Painting	Two Coats of Primer and Two Coats of Synthetic Enamel Paint
15	Motor	100% Imported from Europe

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope
8	Lifting Equipements	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks from confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Vivek
8350570333
For NIHVA Technologies Pvt Ltd