NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Uniqcore Constructions India Pvt Ltd
No - 11/21 Sri Krishna Illam, 12th Avenue
Vaigai Colony, 2nd cross street
Ashoknagar, Chennai -600083

Date : 15.05.2020
Quote NO : SQT.19.20.2543
Kind Attn : Mr. Vanitha.B
Email Id : uniqcoreplanning1@gmail.com
Contact No: **+91 4442139392**

Project Name & Location:

Subject : Quotation for Sectional Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Sectional Door (ASSA ABLOY)	2400	3000	54	2,48,000	1,33,92,000	20,000	10,80,000
2	Sectional Door (ASSA ABLOY)	4000	5000	1	3,54,000	3,54,000	20,000	20,000
				Total		**1,37,46,000**		**11,00,000**
	P&F Charges			3%		**4,12,380**		
	Total Without Taxes					**1,41,58,380**		**11,00,000**
	GST Extra @ 18%			18%		25,48,508		1,98,000
	Total With Taxes					**1,67,06,888**		**12,98,000**
3	Transportation Charges					**Extra At Actual**		
4	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company


GST Pune : 27AAECN0437H1ZM

B) Technical Specification

ASSA ABLOY Motorised Sectional Door







Sr. No	Description	Specification
1	Model No	ASSA ABLOY OH1042P
2	Vision Windows	2 Nos at central panel
3	Opening Direction & Mounting	Standard
4	Opening/Closing Speed	CDM9 0,28 m/s
5	Door Material	GI Steel
6	Panel Thickness	42 mm Square Grid, steel sheet
7	Filling	CFC-free polyurethane
8	Panel colour	RAL 9002 Grey White Powder coated
9	Door sealent	All door sealants made of EPDM rubber, temperature resistant -30/+70
10	Panel Flame Retardent standrad	Flame retardant polyurethane foam according DIN4102-class B2.
11	Water Penetration	EN 12425 class 3
12	Air Permealibity	EN12426 class 3
13	Wind Load	EN21424 class 3
14	Thermal Transittance	EN 12428 1.10W /m2K
15	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
16	Door saftey	Doors equiped with spring break device
17	Incase of Power failuer	Doors to be equiped with quick release fuction
18	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
19	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft
20	Emergency Operation	by Disengagement rope manual
21	Operating Switch	Up/Down Keypad + stopbutton
22	Locks : Lock bolt	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside.
23	Environmental Green Product Declaration Certification	As per ISO 14025 and EN 15804

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 13-14 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd