**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**John Deere India Pvt Ltd**
Sanasawadi
Pune - 412208

**Date : 16.12.2019**
**Quote NO : SQT/19-20/2307**
**Kind Attn : Mr. Sachin Jadhav**
**Email Id :** JadhavSachin@JohnDeere.com
**Contact No: 9922924980**

**Subject : Quotation for High Speed Door RR 3000 ISO.**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |

**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **High Speed Door RR3000ISO** | 4000 | 4500 | 5 | 12,81,000 | 64,05,000 | 15,000 | 75,000 |
| 2 | **High Speed Door RR3000ISO** | 6000 | 6000 | 1 | 15,63,000 | 15,63,000 | 15,000 | 15,000 |
| 3 | **High Speed Door RR3000ISO** | 4000 | 4000 | 2 | 11,95,000 | 23,90,000 | 15,000 | 30,000 |
| 4 | **High Speed Door RR3000ISO** | 4500 | 4500 | 1 | 13,00,000 | 13,00,000 | 15,000 | 15,000 |
| 5 | **High Speed Door RR3000ISO** | 3000 | 4400 | 1 | 12,12,000 | 12,12,000 | 15,000 | 15,000 |
| | | | **Total** | | | **1,28,70,000** | | **1,50,000** |
| 6 | P&F Charges | | | NIL | | | | |
| | **Total Without Taxes** | | | | 1,28,70,000 | | 1,50,000 | |
| | GST Extra @ 18% | | | 18% | 23,16,600 | | 27,000 | |
| | **Total With Taxes** | | | | **1,51,86,600** | | **1,77,000** | |
| 7 | Transportation Charges | | | | Extra at Actual | | | |
| 8 | Unloading Charges @ Site | | | | In Client Scope | | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**Optional Accessories : Windows**

| Sr No | Description | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|
| | | (Row) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Window slats: Lamellas with transparency window slats ( considered two rows per door )** | 20 | 25,000 | 5,00,000 | Included | |

**B) Technical Specification**

| Sr. No | Description | Details |
|---|---|---|
| | | **High Speed Door RR3000ISO** |
| 1 | Door construction: | consists of highly thermally insulated sandwich lamellas consisting of foam (thickness 50 mm) covered by metal sheet trays in silver (RAL 9006). A doubled sealing system links the lamellas ensuring excellent wind and water tightness and a smooth run of the door |
| 2 | Side Frames | Made up with Galvanised Steel Profiles |
| 3 | Thermal transmittance: | Door blade 1,4 W/m²K<br>Complete door min 1,5 W/m²K |
| 4 | Wind resistance: | class 2-3 (EN 12424)<br>DW ≤ 5000 mm: class 3<br>DW > 5000 mm: class 2 |
| 5 | Contactless Winding : | The innovative Disc Drive technology used in the Albany RR3000 ISO supports the door curtain movement thereby ensuring a long service life. The slats are wound onto windling discs without contact. Using this technology, the door can be opened and closed very quickly and with no wear. |
| 6 | Drive Unit : | Gear motor 1,1 KW. Chain drive to reduce mounting space to the side |
| 7 | Temperature range : | -20°C to +40°C (mounting side) |
| 8 | Protection : | IP55 |
| 9 | Control system: | Albany MCC, with vector control technology and boost function at start-up. Graphic display and foil keypad for easy guided operation. Easy access to all important information for operation and service |
| 10 | Control Voltage | 24 V DC |
| 11 | Power supply: | 3/N/PE 380/400/415/440/480 V; 50/60 Hz. |
| 12 | Speed: | Opening / closing up to 2,1 / 0,7 m/s. |
| 13 | Safety device: | Door line photo-cell, drop down protection by integrated balancing system |
| 14 | Manual activation : | by releasing the brake at ground level. Partly opening by means of the pre-stressed tension springs. |
| 15 | Heat transfer coefficient : | Door blade 1,4 W/m²K |
| 16 | **Options :** | **Window slats: Lamellas with transparency window slats** |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 13 - 14 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd