NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Systematic Conscom Ltd
C -1, A & B, First Floor, Sector – 1,
201301 Noida, U.P.

Date : 14.01.2021
Quote NO : SQT.20.21.2474
Kind Attn : Mr. Charan Singh
Email Id : charan.singh@conscom.in
Contact No: 8800544661

Project Name & Location: **Noida, UP**

Subject : Quotation for Retratable Roof

Dear Sir / Ma'am,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size	Qty	Supply and Installation Charges in INR	
			(Nos)	Unit Price	Total Amount
1	Rectratable Roof- Vrindavan Temple.	• 16000 X 15400 X 3000mm • 4 Motors with Machanism • Center Opening • Installation Inclusive •Include dismantling of existing structure	1	98,50,000	98,50,000
2	Rectratable Roof-Vrindavan farmhouse.	• 7400 X 5400 X 1200mm • 2Motors with Machanism • One side Opening • Installation Inclusive	1	18,80,000	18,80,000
			Total		**117,30,000**
			Total Without Taxes		**117,30,000**
			GST Extra @ 18%	18%	21,11,400
			Total With Taxes		**138,41,400**
3		Transportation Charges			**In Client Scope**
4		Unloading Charges @ Site			**In Nihva Scope**

B) **Technical Specification -**

Size:16000 X 15400 X 3000mm- Vrindavan Temple.
1. 6mm Polycarbonate Israel Make embossed clear
2. Profile : Powder Coated AL Frame (As per RAL colour)
3. Guide : Annodized AL Guide
4. Interlocking
5. 4 Nos Motor with Rack and Pinion Arrangement a) Single Phase Bi-directional Motor b) Speed- 09-12m/min c) Power- As per Roof Dimension d) Mechanical Limit Switch e) Rack and Pinion Arrangement -Z16/Molude4/Module6 f) Italian Make BFT Brand
6. Control Panel System
7. Grade 6060 60 X 103.3 X 2.5 Extruded AL Profile
8. Grade 6063 63.3 X 110 X 3.9 Extruded AL Profile
9. Grade 6063 Guide Rail Extruded AL Profile
10.AL RHS 30 X 80 X 3 Support Profile tube
11. EPDM Rubber and Gasket
12. Remote Controlled Mechanism
13. SS Fasteners and SS Fabricated Parts

Size:7400 X 5400 X 1200mm- Vrindavan Farmhouse
1. 4mm Polycarbonate Israel Make embossed clear
2. Profile : Powder Coated AL Frame (As per RAL colour)
3. Guide : Annodized AL Guide
4. Interlocking
5. 2 Nos Motor with Rack and Pinion Arrangement a) Single Phase Bi-directional Motor b) Speed- 09-12m/min c) Power- As per Roof Dimension d) Mechanical Limit Switch e) Rack and Pinion Arrangement -Z16/Molude4/Module6 f) Italian Make BFT Brand
6. Control Panel System
7. Grade 6060 60 X 63 X 2.5 Extruded AL Profile
8. Grade 6063 63.3 X 110 X 2.9 Extruded AL Profile
9. Grade 6063 Guide Rail Extruded AL Profile
10. AL RHS 55 X 25 X 3 Support Profile tube
11. EPDM Rubber and Gasket
12. Remote Controlled Mechanism
13. SS Fasteners and SS Fabricated Parts

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 Profile size and ribs vary according to site dimension

Note: Please find below List which are in Client Scope

Sr. No		Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 1st-March 2021 .

Payment : 60% Advance,35% against delivery & 5% after installation.

Validity : Validity of Offer is 2days from the date of quotation

Warranty : 12 months from the date of supply and 5 years warranty for polycarbonate sheets

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Gaurav Jain on 9766015333**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd