NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Address
ATC Tires Pvt. Ltd. (Member of Alliance Tire Group)
Block No. 53 & 27 C, 2nd Floor, Empire Complex, 414 Senapati Bapat Marg, Lower Parel, Mumbai 400013

Date : 13.01.2020
Quote NO : SQT.19.20.2328
Kind Attn : Mr.Julian Lampert
Email Id : jlampert@atgtire.com
Contact No: 8657818602

Project Name & Location: Telescopic Conveyor, Mumbai

Subject : Quotation for Telescopioc Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Total length of conveyor (mm)	Width Of Conveyor (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Telescopic Conveyor	19000	1900	1	1,150,000	1,150,000	20,000	20,000
2	Barcode scanner (Sick make),Integration & programming with client system , HMI , Onsite Programming & integration			1	400,000	400,000	-	-
			Total			**1,550,000**		**20,000**
3	P&F Charges			3%		**46,500**		
	Total Without Taxes					**1,596,500**		**20,000**
	GST Extra @ 18%			18%		287,370		3,600
	Total With Taxes					**1,883,870**		**23,600**
4	Transportation Charges					**In Client Scope**		
5	Unloading Charges @ Site					**In Client Scope**		

B) Technical Specification

Description	Specification
Total Length of Conveyor	19000 mm
Collapsed Length	7500 mm
Telescopic Length	11000 mm
Width of Conveyor	1900 mm
Width of Conveyor Belt	1200 mm
Conveyor Capacity	75 kg/mtr
Speed	10 mtr/min (Variable speed)
Conveying	Auto/Manual
Telescopic	Auto/Manual
Hydraillic Lifting Support	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1. Installation will start after receiving of Site Readiness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipments are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No		**Remark**
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8- 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Shailendra Saindane on 7709209333**

With Best Regards
Yogita
8530872333
For NIHVA Technologies Pvt Ltd