WORK ORDER

Client
SEZ Biotech Services Pvt Ltd
Address:
Manjari Bk., Tal. Haveli, Pune 412207 (India)

PO Number:	4700064383	**W. O. no-**	SO/20-21/052
PO Dated :	04-Nov-20	**W. O. Date**	04-Nov-20
PO Received Date:	04-Nov-20	**Sales Co ordinator**	Shailesh
Ref. Quotation:	SQT.20.21.2773R2	**Front Sales Person**	Arjun

Dispatch Address:

SEZ Biotech Services Pvt Ltd, Manjari Bk., Tal. Haveli, Pune 412207 (India)

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Rate	Supply	Installation	Total Amount	Dwg. Approval
1	Single Slat Motorized Rolling Shutter	Size : (W)3400 x (H)3950 mm	NO	2				-	Pending

Sr .No.	Specification	GI Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick GI.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm.
12	**Surface finish**	PU paint or Powder coated
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

A) Commerical Terms

1)	**Payment Terms:**	Supply : 100% Against Delivery & Installation : 100% After Installation
2)	**Delivery Date as per PO:**	15 days from the date of PO
3)	**Transportation:**	-
4)	**P&F Charges:**	NA
5)	**Loading:**	Client Scope
6)	**Unloading:**	Client Scope
7)	**Lifting Equipments:**	Client Scope
8)	**Warranty:**	12 Months from date of Supply
9)	**Height arrangement:**	Client Scope
10)	**Electricity Supply:**	Client Scope
11)	**GST:**	Due to SEZ
12)	**Installation Scope:**	NIHVA
13)	**Mode of import:**	NA
14)	**HSS:**	NA
15)	**Documentation Required:**	Standard Handover Documents

Certified that the above work order finalised in presence of:

AGM	SALES	PROJECT	PPC	DESIGN	Date & Time
A.K	A. P.		S.B.		