NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Tata Consumer products Ltd
Tata Steel Industrial Park
Gopalpur, Ganjam District, Odisha

Date : 12.09.2020
Quote NO : SQT.20.21.2685
Kind Attn : Karthik Vidhyasankar
Email Id : Karthik.Vidhyasankar@tataconsume
Contact No: 8861486715

Subject : Quotation for High Speed Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
	High Speed Door RR300 PLUS ALU	4500	3000	1	501,000	501,000	20,000	20,000
	High Speed Door RR392	6000	5000	1	698,000	698,000	20,000	20,000
				Total		**1,199,000**		**40,000**
				P&F Charges	3%	**35,970**		
				Total Without Taxes		**1,234,970**		**40,000**
				GST Extra @ 18%	18%	222,295		7,200
				Total With Taxes		**1,457,265**		**47,200**
				Transportation Charges		**Extra at Actual**		
				Unloading Charges @ Site		**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

High Speed Door RR392

Sr. No	Description	Details
		High Speed DoorASSAABLOY (Albany) RR392(100% Imported products from Europe)
1	Door construction:	High-Speed Roller Door with transparent curtain and blue (similar RAL 5002) reinforcement stripes, optional red (similar RAL 3002). Door with curtain tension.
2	Wind Resistance	Curtain with Tension to the bottom .
3	Drive Unit	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door).
4	Control system	Control system ACS 50 IP 55, for opening and closing speed up to max. 0,8 m/s. Control box lacquered.Control box with Up-Stop-Down button.
5	Power supply	3/(N)/PE/230/400/415 v; 50 Hz
6	Safety	Safety photocell transmitter / receiver inside side columns.
7		Sensor on both Side
8		Push Bottons on both side
9		Lever Operation at Operator Height

High Speed Door RR300 Plus Aluminium

Sr. No	Description	**Albany Make Rapid Roll Up Door RR300 Plus Aluminium (100% Imported with all components – made in Germany)**
	Construction:	Transparent PVC with blue (RAL 5002) or red (RAL 3002) reinforcement stripes. Aluminium, anodized with shafts made of galvanized steel
1	Side Frames :	Aluminium profiles, anodised
2	Drive Unit:	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)
3	Self Opening :	Standard - the door can be opened partially up to 1,8 m by releasing the brake manually.
4	Control system:	Controls ACS 50, IP 55 for opening / closing speed approx. 1,0 m/s. Control box with Up-Stop-Down button.
5	Power supply:	3/(N)/PE/230/400/415 V, 50 Hz.
6	Safety features:	Safety edge, safety photocell Transmitter / Receiver inside side frames, emergency crank and mechanical drop-down protection.
7		Sensor on both Side
8		Push Bottons on both side
9		Lever Operation at Operator Height

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 12-13 Weeks for High Speed Door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact Mr.Sneha Bharane on 8551035333

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd