NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

PRASHANT DESHMUKH & ASSOCIATES
PUNE

Date : 05.02.2021
Quote NO : SQT.20.21.3000
Kind Attn : Er.Maithilee Thakare
Email Id : pdaarchitect@gmail.com
Contact No: 20-24223300 24217555/56

Subject : Quotation for Three Leaf Telescopic Sliding Gate .

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Three Leaf Telescopic Sliding Gate	5500	1800	1	480,000	480,000	20,000	20,000
				Total		**480,000**		**20,000**
			P&F Charges	3%		14,400		
			Total Without Taxes			494,400		20,000
			GST Extra @ 18%	18%		88,992.00		3,600
			Total With Taxes			**583,392**		**23,600**
			Transportation Charges			**Extra at actual**		
			Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Three Leaf Telescopic Sliding Gate

Sr .No.	Specification	Telescopic Sliding Gate
1	Door type	Motorised Three Leaf Telescopic Sliding Gate
2	Master Leaf Size	2600 X 1800 mm
3	1 ST Leaf Size	2600 X 1800 mm
4	2 ST Leaf Size	2600 X 1800 mm
5	Opening Direction	Horizontal - from left to right or reverse
6	Mounting Location area	Inside area
7	Design Pattern	Standard Tubular Design Pattern
8	Outer Frame Tube Sizes	72 x 72 x 3.2mm MS SQ. TUBE
9	Internal Vertical Tube Sizes	25x25x2.6mm MS SQ. TUBE
10	For Post	72 x 72 x 3.2mm MS SQ. TUBE
11	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
12	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings
13	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
14	Painting	Two Coats of Primer and Two Coats of Synthetic Enamel Paint
15	Control Panel	2 Nos Operating Station.(Motor Panel and Security Room)
16	Operation	By Telescopic Mechanism
17	Accessories	1. Limit Switch for Cut out when Gate is fully Closed
		2. Flashing Light
		3. Hooter
		4. Photocell

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 07410169333** For any further Clarification /Information in this Concern.

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd