HORIZON CHUTES PRIVATE LIMITED

Annexure 1 - Offer Summary

Ref.No. : 252620014 /R0		**Date :**	08-04-2025
Supply and Installation of 2 Hrs Fire Rated Doors - 995468	**Kind Attention - Mr. Vijay Tarak**	**Contact No. -** 85510 93333	
Client and Project Name:	**NIHVA TECHNOLOGIES PVT. LTD - NIHVA TECHNOLOGIES PVT. LTD (28 DOORS)**		

Sr. No	Location / Nomenclature	Door Size in MM		Fire Rating	Type	H/w Set	Installation Rate	Supply + Hardware	No Of Doors	Grand Total
		W	H							
1	Double Door	1800	2400	2 HRS FRD	DOUBLE EQUAL LEAF	A	NIHVA SCOPE	41,549	1	41,549
2	Single Door	1000	2400	2 HRS FRD	SINGLE LEAF	B	NIHVA SCOPE	23,610	27	6,37,470

Notes :

1.Refer annexure 2 for Hardware Set and Covering Letter for Material specifications & General Terms and Conditions.

2. FRD - Single Leaf - Frame: Thickness 1.2mm thk Single Rebate: 98.3 X 69 mm. Sheet.Shutter: Thickness 44.5 ± 1.5 mm manufactured in 0.8mm thk. Sheet.

3.FRD - Double Leaf - Frame: Thickness 1.2mm thk Single Rebate: 101 X 69 mm. Sheet.Shutter: Thickness 44.5 ± 1.5 mm manufactured in 0.8 mm thk. Sheet.

4. Finish: Fortune Make Powder Coating standard RAL shades. RAL Code - 3020 - Traffic Red, 7040 - Windows Grey ,7004 - Signal grey,9001 - Off White,9010 - Pure white, 9016 - Traffic white; Additional RAL shades available at revised cost. Delivery timelines may extend for special make & RAL shades.

5.PUF/Sealent filling/ Grouting in the gap between wall and door frame is not in HCPL scope; if required it will charge extra at actual

6. Transportation, Unloading & Mathadi is extra at actual is in your scope.

7. Installation is in NIHVA scope.

8. Payment Terms - 50% advance along with PO, balance 50% before material dispatch.

9. The offer is shared as per the sizes mentioned.Changes in size would lead to price revisions.

Total	**28**	**6,79,019**
Transportation and Unloading		NIHVA SCOPE
Total		**6,79,019**
C-GST	9%	61,112
S-GST	9%	61,112
Grand Total		**8,01,242**