NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

SCON Projects Pvt. Ltd
Office No.1A, Harshal Corner, Plot No.5, Survey
No.78, Left Bhusari Colony, Paud Rd., Kothrud
Pune - 411038 .

Project, Location : Sanand, Ahmedabad

Date : 9.1.2021
Quote NO : SQT.20.21.2937
Kind Attn : Kamlesh Bhagade
Email Id : kamleshb@sconprojects.com
Contact No: 8308809561

Subject : Quotation for Revolving Door and Automatic Sliding Glass Door.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Revolving Glass Door**	3000	2500	1	1,838,000	1,838,000	20,000	20,000
2	**Automatic Sliding Glass Door**	1500	2100	4	161,000	644,000	20,000	80,000
3	**Automatic Sliding Glass Door**	3000	2100	1	203,000	203,000	20,000	20,000
	Total			**6**		**2,685,000**		**120,000**
4	P&F Charges			3%		80,550		
	Total Without Taxes					2,765,550		120,000
	GST Extra @ 18%			18%		497,799.00		21,600
	Total With Taxes					**3,263,349**		**141,600**
5	Transportation Charges					Extra at atcual		
6	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Revolving Glass Door

Sr .No.	Specification	
1	**Model:**	RD150
2	**Internal Diameter - mm:**	3000
3	**Internal Height - mm: 2500**	2500
4	**Total Height - mm: 2700**	2700
5	**Fascia Height - mm: 200**	200
6	**Revolving Doorset:**	3 Door leaves
7	**Design - Door Leaves:**	ASSA ABLOY "Frame" profiles feature soft edge rubber nosing and brush carrier
8	**Design - Outer walls (& NCD if**	ASSA ABLOY "Frame" profiles
	-: OUTER WALLS :-	
9	**Finish - Outer walls (& NCD if**	AAES Standard RAL Finish – Colour to be confirmed.
10	**Glass Type outer walls:**	8.76mm Class 1B1 clear laminated safety glass to EN12600
11	**Night Closing Doors:**	NOT INCLUDED
	-: ROTATING SECTION :-	
12	**Finish - Rotating section RAL:**	AAES Standard RAL Finish – Colour to be confirmed.
13	**Glass type door leaves:**	Standard clear laminated
	-: ACCESSORIES :-	
14	**Ceiling:**	Standard white melamine radially segmented inner ceiling
15	**Lighting:**	LED Spotlights 12 V (White bezel)
16	**Dust protection roof:**	Standard white melamine dust cover
17	**Water resistant cover:**	Water resistant cover to the external half of the canopy only
18	**Emergency Stop:**	1 Stop button Flush mounted
19	**Doorset Lock:**	Euro cylinder
20	**Lighting Control:**	Key switch NOT INCLUDED
21	**Programme Switch :**	Flush mounted 2 Position key switch & reset push button
22	**Activation:**	PIR motion sensor flush fixed under the canopy fascia
23	**Doorset bottom rail safety:**	Monitored Pressure Sensitive Protective Edge in rubber safety nosing
24	**Safety in Rotating part:**	Presence detection to EN 16005 as listed below
25	**Outer Wall leading mullion:**	Monitored Pressure Sensitive Protective Edge in rubber safety nosing
26	**Doorset outer stiles:**	Monitored Pressure Sensitive Protective Edge in rubber safety nosing



BI PARTING AUTOMATIC SLIDING DOOR

Sr .No.	Specification	
	POWER DRIVE	
1	**Motor**	High performance and heavy duty DC motor with integrated encoder and gearbox
2	**Power Supply**	170-260 V AC 50-60 Hz
3	**Power Consumption**	170 W
4	**Protection Class**	IP22
5	**Carrying Capacity**	170 Kg for single leaf, 240 Kg for double leaves
6	**Clear Opening**	2,100 x 3,000
7	**Operator Chassis Size**	125 x 168 mm , Aluminium
8	**Carrier Assembly**	Two carrier assembly for each leaf, (2 main and 1 balancing wheel for each carrier assembly)
9	**Trigger Belt**	Special trigger belt design for maximum safety and endurance and minimum noise level
	MICROPROCESSOR	
10	**Working Temperature**	- 20* C + 50* C
11	**Position Selector**	Digital , 6 user positions, LCD touch screen
12	**User Modes**	Auto , Open , In , Out , Locked , Half Opening
		Opening Speed, Closing Speed, Hold Open Time, Half Opening Distance, Opening, Direction, Installer
13	**Installer Settings**	Password, User Password
14	**Obstacle Detection**	Permanent obstacle detection in both opening and closing cycles.
15	**Energy Saving**	Short braking distance during opening and closing cycle for energy saving
16	**Interlocking**	2 doors can be operated using interlocking mode
17	**Resetting**	Can be performed using digital position selector without opening operator cover
18	**Compatibility**	Compatible with fire alarm and access control systems
19	**Fault Monitoring**	Error codes are shown on the digital position selector screen.
	SENSOR	
20	**Safety**	3D infrared curtain photocell
21	**Opening**	Radar
22	**Combiner (Opening + Safety)**	Opening radar with integrated 3D infrared curtain photocell, Energy saving, EN16006
	DOOR LEAF	
23	**Frameless**	With 2 point fittings per door panel
24	**Operator Mounting**	On glass panel provided by others

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd