NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No -SQT/19-20/1680R **Date :14.06.2019**

IndoSpace Development Management Pvt. Ltd.
One Indiabulls Centre, 11th Floor,
Tower 2A, Senapati Bapat Marg,
Elphinstone Road, Mumbai - 400013, India

Kind Attn : Mr. Tushar Dhande
Email ID : tushar.dhande@indospace.in
Contact No : 8879311890

Project Name And Location : Khopoli .

Subject : Quotation for Rolling Shutter and Dock Bumper.

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Gear Operated Rolling Shutter** **Technical Specifications:** **• GI Slat : 1 mm Thick** **• Profile : Curved Type Profile with heavy duty Shaft** **• Hood Cover & Motor Cover : 0.9 mm Thick GI material** **• Gear Assembly** **• With Painting** **(Supply + Installation + Transportation + Scaffolding)**				
1	Size (W) 2445 mm x (H) 3000 mm	28	No	58,000	1,624,000
2	Size (W) 4000 mm x (H) 5000 mm	4	No	115,000	460,000
				Total	2,084,000
B	**Dock Bumper** **(Supply + Installation)**				
1	Size (W) 150 mm X (D)80 mm X (H) 400 mm	19(Pair)	No	5,500	104,500

GST Pune	**27AAECN0437H1ZM**	**Grand Total**	**2,188,500**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	Nil.
3	**Freight Notes**	:	Inclusive.
4	**Delivery**	:	6-7 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Insurance**	:	Extra As applicable
8	**Tax**	:	GST@18% Extra
9	**Validity**	:	Validity of Offer is 15 days from the date of quotation
10	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact Arjun Patil on **8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd