NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Anmol Industries Ltd.
Maity Para, Delhi Road,Dunkuni
Hooghly, West Bengal. 712311

Date : 24.01.2022
Quote NO : **MHE_21.22.0054R**
Kind Attn : Mr. Bimal Chaudhary
Email Id : bimal@anmolindustries.com
Contact No: 98300 53709

Project Name & Location: Anmol Industries Ltd. West Bengal

Subject : Quotation for Telescopic Truck Loader/Unloader Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Truck Loader/Unloader Conveyor with Counting system (30 feet Container)** • Total Length- 14.5mtr (Fixed-5.5mtr, Extended-9mtr) • Capacity- 40-50 boxes/min • Light infront of the conveyor	**4**	**15,60,000**	**62,40,000**	**85,000**	**3,40,000**
2	**Telescopic Truck Loader/Unloader Conveyor with Counting System (40 feet Container)** • Total Length- 17mtr (Fixed-5.5mtr, Extended-11.5mtr) • Capacity- 40-50 boxes/min • Light infront of the conveyor	**1**	**17,45,000**	**17,45,000**	**85,000**	**85,000**
3	**Inclination conveyor to Match 850mm Height of Telescopic Conveyor with separate Drive**	**5**	**75,000**	**3,75,000**	**20,000**	**1,00,000**
	TOTAL EXCLUDING TAXES			**83,60,000**		**5,25,000**
4	GST Extra @ 18%	18%				**Extra At Actual**
5	P&F Charges	3%				**Extra At Actual**
6	Transportation Charges (40ft container)					**Extra At Actual**
7	Insurance Charges					**Extra At Actual**
8	Software require for Integration & synchronisation					**In Client Scope**
9	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Truck Loader/Unloader Conveyor

Sr. No.	Parameters	Specification
1	Material to be conveyed	Biscuit Boxes
2	Dimension of Box (LxBxH)	457 mm X 254 mm X 457 mm
3	Weight of box	Max. 6.5 Kg
4	Capacity	40-50 boxes/min
5	Belt Width	400 mm
6	Belt Type	2 Ply 3.2 mm PVC
7	Belt Speed	15-30 mtr/min
8	Telescopic Speed	8-18 mtr/min
9	Conveyor Type	Collapsible boom type hinged Telescopic belt conveyor
10	Length Of Conveyor	Fixed Length : 5500 mm and 5500 mm Telescopic (Expanded) : 9000 mm and 11500 mm Total Length : 14500 mm and 17000 mm
11	Main Body Of Conveyor	MS Powder coated
12	Direction	Both Forward and Reverse direction
13	Max. Working height	850 mm
14	Speed adjustment	VFD (Schneider / Allen Bradley/Delta)
15	Gear Box	Bonfiglioli
16	Driven Motor Make	Bonfiglioli /CG/BBL , IE2
17	Movement	Fixed (wheel not require)
18	Counting System	Guide to be provided at Fixed conveyor for alignment of the boxes. Sensor provision for counting boxes.
19	Light Provision	At End of the Conveyor
20	Communication	Through Ethernet Network system.

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an adiitional cost.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8-9 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch

Validity : Validity of Offer is 90 days from the date of quotation subjest to variation in raw material price.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Vijay Tarak on 85510 93333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd