WORK ORDER

NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Client
IKEA India Pvt.Ltd.
Address:
IKEA India Private Limited Nagasandra Village, Yeshwanthpur Hobli Bangalore Store Survey. No 12 /13, Behind Nagasandra Metro Station, IN 560068 Bangalore GST 29AADCI3006N1ZG

PO Number:	2102065612	W. O. No-	SO/21-22/0119
PO Dated :	05.01.2022	W. O. Date	07.01.2022
PO Received Date:	05.01.2022	Sales Co ordinator	Pratibha
Ref. Quotation:	AS_21.22.0050	Front Sales Person	Mr. Vijay Tarak

Dispatch Address:

IKEA India Private Limited
Nagasandra Village, Yeshwanthpur Hobli Bangalore Store
Survey. No 12 /13, Behind Nagasandra Metro Station,
IN 560068 Bangalor GST 29AADCI3006N1ZG

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Rate	Amount	Dwg. Approval
1	**Manual Mobile Scissor Lift Table**	1.Platform Size = 1400 mm L X 900 mm W 2.Capacity = 500 KGS 3.Shut Height = 400 mm 4. Max Height = 1300 mm 5.Lift Height = 900 mm 6. Hand pump for lifting operation 7.Push pull handle provided for Manual Movement 8.Wheels : Dia 150 x 50 (PU Wheels) 9. RAL SHADE FOR PAINT - RAL 1004 GOLDEN YELLOW 10. MOVEMENT BY MANUAL TOWING 11. LIFTING BY HYDRAULIC CYLINDER 12. OPERATION BY HAND OPERATED PUMP 13. DETACHABLE TYPE SAFETY RAILING ON TWO LENGTH SIDE, (PLAIN SHEET TOP PLATFORM FIXED WITH 5 MM THIK WOOD & BLACK VELVET CLOTH) 14. PU WHEELS FOR MOVEMENT- 2 WHEEL NO BRAKE & 2 SWIVEL WITH BRAKE 15. FINISH - PAINTING QD ENAMEL PAINT 16. RAL SHADE FOR PAINT - RAL 1004 GOLDEN YELLOW 17. OVERALL SIZE OF PRODUCT - 1750(L) X 900(W) X 1050(H) 18. LIFTING BY HAND PUMP & LOWERING BY HAND 19. HAND PUMP MAKE - DOWTY HAND PUMP WITH RESERVOIR 20. LIFTING TIME - 30 TO 45 SEC 21. MAXIMUM HAND LOAD - 23 KG - REF FROM CATALOGUE	**NO**	**2**		-	**Pending**

A) Commerical Terms

1)	**Payment Terms:**	100% after 30-days from delivery of products on-site
2)	**Delivery Date as per PO:**	5-6 weeks
3)	**Transportation:**	In Client Scope (Pls refer Addendum)
4)	**P&F Charges:**	Extra @ 3%
5)	**Loading:**	NIHVA scope
6)	**Unloading:**	In Client Scope (Pls refer Addendum)
7)	**Lifting Equipments:**	NA
8)	**Warranty:**	12 months from the date of installation
9)	**Height arrangement:**	NA
10)	**Electricity Supply:**	In Client Scope
11)	**GST:**	Extra @ 18%
12)	**Installation Scope:**	NA
13)	**Mode of import:**	
14)	**HSS:**	
15)	**Documentation Required:**	Standard Handover Documents

Certified that the above work order finalised in presence of:

AGM	SALES	PROJECT	PPC	DESIGN	Date & Time
A.K.	**V.T.**	**S. M.**	**S.B.**	**G.P.**	**06-01-2022**