NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

IndoSpace Industrial Parks Pvt Ltd.
One Indiabulls Centre, 4th Floor, Tower 2B, Senapati Bapat Marg,
Elphinstone Road, Mumbai - 400013,
Maharashtra, India

Date : 28.05.2020
Quote NO : SQT/19-20/2540
Kind Attn : Mr Tushar Dande
Email Id : tushar.dhande@indospace.in
Contact No: 8879311890

Subject : Quotation for Swing Gate_Rohan city space B100

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**MOTORISED DOUBLE LEAF SWING GATE**	5000	1800	2	2,55,000	5,10,000	15,000	30,000
2	**MOTORISED DOUBLE LEAF SWING GATE**	6000	1800	1	2,69,000	2,69,000	15,000	15,000
3	**MANUAL WICKET GATE**	1500	1800	2	40,000	80,000	5,000	10,000
			Total			**8,59,000**		**55,000**
4	P&F Charges			3%		25,770		
	Total Without Taxes					8,84,770		55,000
	GST Extra @ 18%			18%		1,59,258.60		9,900
	Total With Taxes					**10,44,029**		**64,900**
5	Transportation Charges					Extra at Actual		
6	Unloading Charges @ Site					In Client Scope		

B) TECHNICAL SPECIFICATION - Swing GATE

NIHVA make – Motorized Double Leaf Swing Gate	
Mounting Location area	Inside area
Design Pattern	Standard Tubular Design Pattern
Outer Frame Tube Sizes	72 x 72 x 3.2mm MS SQ. TUBE
Internal Vertical Tube Sizes	25 X 25 X 2.6 THK MS SQ. TUBE
Gap Between Tubes	125 MM
Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
El motor make	BFT – Italy (100% imported)
Operating Switch	Push Button from inside
Safety	Flashing Light

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd