RMK INFRASTRUCTURE PVT.LTD.

Address-RMK Square Shop No. 2992/1,Vishnupuri , Near Nutan Polytechnic Collage,Talegaon Chakan Road, Talegaon Station Tal. Maval Dist. Pune. | **GST No- 27AAFCR0774G1ZB**

Ref: RMK/WO /2020/ 182 **Date- 18-Jun-20**

Name of contracting firm		:- NIHVA Technologies Pvt. Ltd.
Name of Authorized Person		:- Mr. Arjun Patil
Type of firm		:- Pvt. Ltd.
Temporary Address/Permanent address		:- 187, G- Block, 1st Floor, above Renault Showroom, Thermax chowk, MIDC, Chinchwad, Pune- 411019
Contact details	Mob 1	:- 8551091333 / 8551096333
	Email ID	:- sopport@nihva.com
GST No		27AAECN0437H1ZM
Pan card photo copy attached		☐
Address proof attached		☐
Work specialization		:- Mannual Rolling Shutter and Automatic Sectional Door

Subject: - Work order for Design, Drawing, Supply & Installation of Mannual Rolling Shutter and Automatic Sectional Door at Nidar-Cooper Shed, Navlakh Umbre Talegaon dabhade, Pune.

Contact Person:- Mr. Nisar Magdum- 7030940677, Mr. Jaywant Kumbhar- 9552531168

A) Safety & environment requirements: -

1. All the Operators/labours should be age of above 18 and below 55 years, no child labour shall be permitted at work site.
2. You will have to follow all Safety Measures at work site, and all PPE's for your workers is in your scope of work.
3. The equipment used by you must be in good working condition at all times.
4. All the equipment & operator needing RTO, registration will be duly registered with RTO, without any cost to us.
5. You will be responsible for all the accidents, mishaps occurring on your work site due to your equipment and you will attend to all legal matters/police matters in that respect without any cost to us.
6. Do not cut off any trees/plants without prior written permission by "RMK INFRASTRUCTURE PVT.LTD".
7. All Required safety PPE's & Equipments will be in NIHVA Technologies Pvt. Ltd. scope.

B) Statutory requirements: -

1. Electricity will be provided at one point by company, further any arrangements for works is in your scope of work.
2. You will have to meet all the statutory requirements of Government in respect of labour laws. You shall also submit one copy of such documents i.e. labour License, Workmen Compensation Insurance Policy/ESI, Migrant Certificate, Provident Fund, Professional Tax etc. as per your scope of work.
3. You have to maintain the attendance record; wages register of your labours and submit the same to us every month.
4. You will bear all the insurance charges for your manpower and equipment.
5. Arrangement & cost of Accomodation, fooding to your workers is your responsibility.
6. Contact person of "RMK INFRASTRUCTURE PVT.LTD." for all of your matters will be discussing to authorize persons (Related to bill- Billing department head, related to accounts- accounts head, and related to technical - site head).
7. For all matters related to this work order, legal jurisdiction will be PUNE.

C) Commercial Terms: -

1. For executing the work entrusted to you, we will not provide any equipment which is deemed to be deployed by you for the item of work. In case you need any equipment either owned by us or hired by us, we may make the same available to you if possible, the hire charges were will be debited to your account for period of use.
2. All accessories, spare parts, tyres etc. as may be required for normal operation and for maintenance / repairs of the Machinery shall be provided by you at your cost and no extra charges shall be payable to you on this account.
3. This contract will be valid for an initial period of 1 Years from the date of this work order, which we may extend for a further suitable period depending on our requirements, for which we will give you at least 30 days advance notice. In case you will not be interested in such an extension of this contract, you shall give us minimum 30 days advance notice to enable us to make alternate arrangements.
4. We reserve our right to discontinue your services with prior notice of 24 hours.
5. You will not be paid any idling charges for your equipment or labour for any reason. You will be paid only for the quantity of work done as per the rates given in annexure to this work order.
6. In case of any dispute, the same will be referred to the Project Manager, "RMK INFRASTRUCTURE PVT.LTD.".-In charge of this project-whose decision shall be final and binding.

D) Payment condition: -

1. The rates of works entrusted to you and to be carried out by you will be as per schedule of rates in annexure.
2. Bill Submission Date- Every Month bill will be submitted by date 1st to 3rd day of month.
3. Your Payment will be made **after one month from the date of bill submission** with M.B. on actual measurement basis duly certified by our site engineer & billing department head.

I have read all the above terms &condition and are accepted to me.

For, NIHVA Technologies Pvt. Ltd. **For, M/S.RMK INFRASTRUCTURE PVT.LTD.**

Authorized signatory

Coordinator	Billing	Tender	Auditor	Authorized signatory
Nisar	Gunjan	Sachin	R. Patel	RRK Sir

4 The payment terms & other conditions are as follows.

Sr no.	Description	Percentage payment release on Basic Contract Value
a	Advance against – 30% Against Submission of A) Advance against Security Cheque of same amount B) Shop Drawing submission and approval from client	30%
c	After Phasewise (within 2 Lot Only) delivery of material at site within 1 week or prior to installation whichever is earlier	60%
d	After Hiranandani completion certificate to RMKIPL for Rolling shutter and Automatic Sectional Door works and on submission of A) Original BG valid for 12 Months from completition certificate B) Warrenty/Gurranty certificate for the Validity of 12 Months from Handing over	10%
	Total	**100%**

5 For hiring machinery agencies PVT Ltd, Partnership, Ltd, proprietary & individual firms 2% income tax will be deducted from your each running bill and TDS certificate will be issued to you at the end of each financial year.

6 This work order is being issued to you in duplicate. You are requested to sign one copy and return it to us immediately in token of your acceptance of this work order.

Annexure- 'A'

Sr no.	Item Description	TYPE	Unit	Quantity	Rate	Amount
1	**Rolling Shutter- Design, Supply & Installation**					
	Mannual Rolling Shutter:- **Performance Characterstics** Mannual Rolling Shutter with MS Laths with thickness of 1mm Mounting Location Area:- Inside area / Outside Area Curtain Panel:- The Panel made of 1.0mm thick MS Curtain Panel Size:- 75mm Wide Curtain Profile:- Curved Bottom Profile:- MS Plate 100mX 2.5mm thick with angle stiffner Side Guide Profile:- MS wind lock Guide profile 65mm- 150mm x 3mm thick (as per opening width dimention) Roller Shaft:- MS Tubular pipe with flange & Machined shaft at the ends Pipe dia- 100 to 300mm as per w x h Side Brackets:- MS Plate 3mm to 10mm thick, as per the Opening dimension Hood Cover:- Made of GI sheet thickness 1.2mm GF mm with 25X25X3mm angle Stiffner Surface Finish:- PU paint or Powder Coated					
1.1	Manual rolling shutter Clear Opening 2400mm wide x 3000 mm tall (Colour - As per approved Shop Drawing from both sides)		Each	2.00	55,965	1,11,930
1.2	Manual rolling shutter Clear Opening 2400mm wide x 3600 mm tall (Colour - As per approved Shop Drawing from both sides)		Each	1.00	58,695	58,695
1.3	Manual rolling shutter Clear Opening 2500mm wide x 3600 mm tall (Colour - As per approved Shop Drawing from both sides)		Each	1.00	62,335	62,335

I have read all the above terms &condition and are accepted to me.

For, NIHVA Technologies Pvt. Ltd. **For, M/S.RMK INFRASTRUCTURE PVT.LTD.**

Authorized signatory **Coordinator Nisar** **Billing Gunjan** **Tender Sachin** **Auditor R. Patel** **Authorized signatory RRK Sir**

Ref: RMK/WO /2020/ 182 **Date- 18-Jun-20**

Sr no.	Item Description	TYPE	Unit	Quantity	Rate	Amount
2	**Automatic Sectional Door- Design, Supply & Installation**					
	Door type:- Automatic Sectional Door for Internal Application Model No:- ASSA ABLOY OH1042P Opening Direction & Mounting:- Vertical Opening/Closing Speed:- CDM 9.0, 28m/s Door Materials:- GI Steel Panel Thickness:- 42mm Square Grid, steel Sheet Filling:- CFC-Free Polyurethane Door Sealent:- All Door sealent made of EPDM rubber, temperature resistance-30/+70 Water Penetration:- EN 12425 class 3 Air Permeability:- EN12426 Class 3 Thermal Transisttance:- EN12428 1.10W/m2K Bottom sealing:- Bottom of the door to be equiped with three lip sealing made of oil resistance EPDM Rubber Door Safety:- Doors equiped with spring break device In-case of Power Falure:- Door to be equiped with quick release function Operator Power Communication:- Operator to have a maximum power of 0.37KW and a standby consumption of maximum 15W Drive Unit & Mounting Type:- Single phase 230V direct drive on shaft Emergency Operation:- By Disengagement rope manual Operating Switch:- Up/ Down Keypad + Stopbutton Locks: Lock Bolt :- The Lock Bolt Locks the door from the inside, without the use of a key. The lock bolt is not visible from the Outside Enviromental Green Product Deciaration Certification:- As per ISO 14025 and 15804					
2.1	Automatic Sectional Door with vision Clear opening 2400mm wide x 3000 mm tall (Colour - As per approved Shop Drawing from both sides) **- Vertical Lift**		Each	3	2,02,930	6,08,790
2.2	Automatic Sectional Door with vision Clear opening 2400mm wide x 3000 mm tall (Colour - As per approved Shop Drawing from both sides) **- Horizontal Lift**		Each	1	2,12,030	2,12,030
					Total	**10,53,780**

Note: The above mentioned rates are inclusive of all applicable taxes Government Levies, all statutory compliances, charges of local authorities etc. complete. Only GST will be paid extra as applicaable

Special Condition:-

1	If it is observed or noticed that you are exceeding the above mentioned rates, please note that the excess amount will be debited to your account. We will not entertain any explanations.
2	**The Entire Project duration for Rolling Shutter, Automatic Sectional Door are 3 weeks. (including Design, supply & installation complete work) from Work order date.**
3	Transportation of Materials upto working Place is in Contractor Scope.
4	Design, Preparation of Drawing its approval, manufacturing, packing, loading,transportation,transit insurance, unloading, shifting (site to site), crane required during installation if required & installation complete all work is in your scope of work. We will provide only space for storage. Security of your material is in your scope of work.
5	Scaffolding done by NIHVA , RMKIPL only supply materials on free of Cost.
6	You should follow all safety rules & regulation setup by RMKIPL & Hiranandani.
7	You should submit the all satutary documents regarding the safety purpose before starting of work.
8	Warranty for mechanical & electrical parts with maintenance of shutters is for 12 Months.
9	Material should be as per Indian standard code specifications & as per IS 6248.

I have read all the above terms &condition and are accepted to me.

For, NIHVA Technologies Pvt. Ltd. **For, M/S.RMK INFRASTRUCTURE PVT.LTD.**

Authorized signatory **Coordinator** **Billing** **Tender** **Auditor** **Authorized signatory**
Nisar **Gunjan** **Sachin** **R. Patel** **RRK Sir**