NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Tech Expert Engineering Pvt Ltd
116, Siddharth Towers, First Floor,
Karve Road, Kothrud, Pune - 411038 India.

Date : 12.08.2020
Quote NO : SQT.19.20.44
Kind Attn : Mr. Mr.Umesh Salunkhe
Email Id : purchase1@techexpertindia.com
Contact No: 9860296818

Project Name & Location: Pune

Subject : Quotation for Rolling Shutter .

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Motorised Rolling Shutter**	4000	9000	1	2,96,000	2,96,000	25,000	25,000
2	**Safety Catch & Structure for 4000 mm X 9000 mm**			1	75,000	75,000		
3	**Motorised Rolling Shutter**	3000	6000	1	1,51,000	1,51,000	25,000	25,000
4	**Safety Catch & Structure for 3000 mm X 6000 mm**			1	65,000	65,000		-
				Total		**5,87,000**		**50,000**
3	P&F Charges on Total Supply Value			3%		**17,610**		
	Total Without Taxes					6,04,610		50,000
	GST Extra @ 18%			18%		1,08,829.80		9,000
	Total With Taxes					**7,13,440**		-
4	Transportation Charges					**In client scope**		
5	Unloading Charges @ Site					**In client scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA Make Motorised Rolling Shutter





Sr. No	Description	Specifications
1	**Rolling Shutter**	Motorised Rolling Shutter with GI steel of thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Curtain Panel**	The panel made of 1.0mm thick GI steel
4	**Curtain panel size**	75mm wide
5	**Curtain Profile**	Curved
6	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
7	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
8	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
9	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension
10	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GI mm with 25x25x3mm angle stiffener
11	**Surface finish**	Powder coated
12	**Drive Unit & Mounting Type**	Motor - Indirect Mounting, Jielong Make

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 4 - 5 Weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333.**

With Best Regards
Varsha
85510991333
For NIHVA Technologies Pvt Ltd