NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Ador Powertron Ltd.
51, D-II, Ramnagar Complex,
MIDC Chinchwad, Pune 411019, India

Date : 17.03.2020
Quote NO : SQT.19-20.2382
Kind Attn : Mr. Subham De Sarkar
Email Id : safety@adorpower.com
Contact No : 9123035422

Project Name & Location: Scissor Lift and Pune

Subject : Quotation for PIT MOUNTED SCISSOR LIFT and Tilting Trolley

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**NIHVA Scissor Lift Capacity : 1 ton**	6000	1500	1	2,45,625	2,45,625	20,000	20,000
2	**NIHVA Scissor Lift Capacity : 2 ton**	750	2000	1	3,74,688	3,74,688	20,000	20,000
3	**NIHVA Tilting trolley Capacity : 300 kg**	1000	2000	1	1,48,876	1,48,876	20,000	20,000
				Total		**7,69,189**		**60,000**
	P&F Charges			3%		**23,076**		
	Total Without Taxes					**7,92,265**		**60,000**
	GST Extra @ 18%			18%		1,42,608		10,800
	Total With Taxes					**9,34,872**		**70,800**
	Transportation Charges					**In Client Scope**		
	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA Scissor Lift

Sr. No	Description	Specifications
1	Type of Mounting	Manual Mobile
2	Capacity	1 ton
3	Platform size	1500L x 600W
4	Shut ht	450 mm
5	Lift ht	1800 mm
6	Max ht	2250 mm
7	Power pack	1HP,3Phase
8	Wheels	dia 150 x 50 (sw castor & fix wheel)
9	Color	Golden Yellow (RAL 1004) std
		Up & down control panel on the scissor platform along with main panel (with 5 mtr cable) on the wall

NIHVA Scissor Lift

Sr. No	Description	Specifications
1	Type of Mounting	Manual Mobile
2	Capacity	2 ton
3	Platform size	2000L x 750W
4	Shut ht	550 mm
5	Lift ht	1950 mm
6	Max ht	2500 mm
7	Power pack	3 HP, 3Phase
8	Wheels	dia 200 x 50 (sw castor & fix wheel)
9	Color	Golden Yellow (RAL 1004) std
		Up & down control panel on the scissor platform along with main panel (with 5 mtr cable) on the wall

NIHVA Tilting Trolley

Sr. No	Description	Specifications
1	Type of Mounting	Manual Mobile
2	Capacity	300 kg
3	Platform size	2000L x 1000W
4	Shut ht	450 mm
5	Tilting degree	90 degree
6	Wheels	Dia 125 x 40 (sw castor & fix wheel)
7	Power pack	1HP,3PHASE AC POWER PACK
8	Color	Golden Yellow (RAL 1004) std
		Up & down control panel on the scissor platform along with main panel (with 5 mtr cable) on the wall

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks for Scissor Lift from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain 8551092333.**

With Best Regards
Samruddhi
7410175333
For NIHVA Technologies Pvt Ltd