Sales Quotation

Quotation No - SQT/18-19/1365R3 **Date : 3.6.2019**

Shubhshree
Aurangabad

Kind Attn: Mr. Nagesh R. Kulkarni
Email ID: nageshkulkarni@shubhshree.co.in
Contact No: 9860906328

Project Name And Location : Endress Hauser Flowtech Aurangabad

Subject: Quotation for Motorised Rolling Shutter, Dock Leveller, Scissor Lift, Wicket Gate

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**NIHVA Make Dock Leveller** **• 2 cylinder for Deck & 1 cylinder for LIP Operator by Standard Control Panel (Deck Up / Down / Lip Up / Down)** **• Rubber Bumpers** **• Capacity - 15 Ton** **Supply + Installation**				
1	Size : (W) 2000 mm X (L) 2500 mm	4	No	240,000	960,000
				Total	**960,000**
B	**Scissor Lift - NIHVA Make** **Hot Dip Galvanized** **Capacity : 15 ton (6 ton udl)** **Platform : 2500L x 2000W** **Power pack : 15HP, 3PH** **Shut ht : 1000 mm** **Max ht : 2200 mm** **Lift ht : 1200 mm** **Railing : 900 mm ht both length side** **Color : Golden Yellow (RAL 1004)** **Supply + Installation**				
1	Size : (W) 2000 mm X (L) 2500 mm	4	No	1,202,320	4,809,280
				Total	**4,809,280**
C	**Motorized Rolling Shutter : NIHVA Make** • GI Slat:1 mm Thick • Curved Type Profile with heavy duty Shaft, Guide, Hood Cover • Motor - Indirect Drive • Painting **Supply + Installation**				
1	Size : (W)2500 mm x (H)4000 mm	7	No	100,800	705,600
2	Size : (W)4000 mm x (H)4000 mm	4	No	126,500	506,000
				Total	1,211,600
D	**Wicket Gate : NIHVA Make** **Supply + Installation**				
1	Size: (W) 1500 mm X (H) 1800 mm	1	No	40,000	40,000
				Total	**40,000**

GST Pune	**27AAECN0437H1ZM**	**Total**	**#REF!**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	NIL
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	5-6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST Extra @ 18%
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

For any concern in this regards please feel free to contact Mr. Ravindra Kharat on + 91 7410169333

With Best Regards

Varsha

8551091333

For NIHVA Technologies Pvt Ltd