NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Tenneco India
Pune

Date : 17.06.2021
Quote NO : AS_21.22.0015
Kind Attn : Mr. Shrikanat Malave
Email Id : SMalave@Tenneco.com
Contact No: 9922946534

Project Name & Location: Pit Mounted Hydraulic Scissor Lift, Pune

Subject : Commercial Offer for Pit Mounted Hydraulic Scissor Lift

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size	Qty	Supply Charges in INR		Installation Charges in INR	
		Working Platform (in mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Pit Mounted Hydraulic Scissor Lift**	1950 W mm X 3500 L mm	1	5,20,740	5,20,740	20,000	20,000
			Total		**5,20,740**		**20,000**
		P&F Charges on Total Supply Value	3%		**15,622**		
		Total Without Taxes			**5,20,740**		**20,000**
		GST Extra @ 18%	18%		93,733		3,600
		Total With Taxes			**6,14,473**		**23,600**
2		Transportation Charges					**Extra At Actual**
3		Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification -

Pit Mounted Electro-Hydraulic Scissor Lift

Sr. No	Description	Specifications
1	**Capacity**	1.5 TON
2	**Platform Size**	1950 W mm X 3500 L mm
3	**Shut Height**	1500 mm
4	**Max Height**	6500 mm
5	**Lift Height**	5000 mm
6	**Paint (RAL 1004)**	Golden Yellow
7	**POWERPACK**	3 HP
8	**HYDRAULIC CYLINDERS**	2 NOS OF CYINDER BORE 50 MM STROKE 1600MM
9	**MANUAL LIP ON ONE SIDE &SAFETY RAILING WITH DOOR OF HEIGHT 1000 MM**	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 7 -8 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact Mr. Rohit Kadgave 7410175333

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd