NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No -SQT/19-20/1870 **Date 27.07.2019**

Address
Royal Orchid Golden Suites
Kalyani Nagar Pune

Kind Attn: Mr.Chabukswar
Email ID: purchase.pune@royalorchidhotels.com
Contact No: 9960608334

Project Name And Location : Retractable Roof, kalyaninagar Pune

Subject : Quotation for Motorized Roof.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Motorized Retractable Roof** **Technical Specifications:** **• Polycarbonate compact clear/Embossed 3.0 mm Thick** **• Profile : Powder Coated AL Frame (as per RAL colour)** **• Guide : Annodized AL Guide** **• Drive : Rack and Pinion Mechanism** **• Interlocking**				
1	Size (W) 10700mm x (L) 5740 mm x (H) 1000 mm (Supply + Installation)	1	No	8,70,000	8,70,000
				Total	8,70,000

B	**Motorized Fabric Roof** **Technical Specifications:** **• Fabric : Ferrari Fabric** **• Profile : AL Frame (as per RAL colour)** **• Guide : AL Guide** **• Drive : Customize motor, AL bracket holder** **• Interlocking**				
1	Size (W) 10700mm x (L) 5740 mm x (H) 1000 mm (Supply + Installation)	1	No	13,40,000	13,40,000
				Total	13,40,000

GST Pune	**27AAECN0437H1ZM**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Civil/structural changes required on site is in client's scope.
3. Electrical Supply on the site single phase/three phase points at different places.
4. Provide electrical cables near to the installation machinery
5. Fork lift/crane to be provided if required .
6. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement.
2. The dimension is considered on the basis of CAD file shared and it only shows cut-out measurement (not the actual roof dimesnion).
3. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
4. Billing will be as per the supply of material ,not as per site measurements.
5. Some cut-out are asymmetric so a rough dimension is depicted for the reference.
6. It is exclusive of structural costing

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@ 3% of Total supply value
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	5-6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST@18% Extra
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply and 10 years warranty for polycarbonate sheets.

Please feel free to Contact **Mr. Gaurav Jain** on +91-9680117657 For any further Clarification /Information in this Concern.

With Best Regards
Pradip
7709586333
For NIHVA Technologies Pvt Ltd