Sales Quotation

Quotation No - SQT/19-20/1633R **Date : 16.05.2019**

MACON ENVIRO TECHNOLOGIES PVT. LTD
203, ASHAR MILLENNIA
Ghodbunder Road, Thane-West,
Mumbai, Maharashtra-400607,India.

Kind Attn: Mr. Debabrata Acharya
Email ID: d.acharya@maconenviro.com
Contact No: 8249358156

Project Name And Location : MACON ENVIRO TECHNOLOGIES PVT. LTD Mumbai

Subject : Quotation for Motorized Sliding Gate

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Single Leaf Motorised Sliding Gate** **(Supply + Installation)**				
	Sliding Gate - (W) 4950 mm x (H) 2700 mm • **For Post- SQ. TUBE 100x4 mm** • **Outer Frame- SQ. TUBE 100x4 mm** • **Inner Frame - SQ. TUBE 49x2.9 mm** • **Gap Between tubes -150 mm TYP.**				
1	**Size (W) 4950 mm x (H) 2700 mm**	1	No	412,000	**412,000**

B	**Single Leaf Motorised Sliding Gate** **Only Automation** **Motor** **Photocell** **Flashing Light** **Rack & Pinion** **Electrical wire & accesories** **(Supply)**				
1	**Size (W) 4950 mm x (H) 2700 mm**	1	No	127,000	**127,000**

GST Pune	**27AAECN0437H1ZM**

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places.
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required .
5 Scaffolding require for Installation it is in client scope.

Limit of Supply

1 Provide place to store the material to be installed .
2 Be responsible for the safe custody of all material.
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers.

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2
In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel.

Client Scope

1 Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@ 3% of Total supply value
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST Extra 18%
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

If there is any query please feel free to contact Mr. Arjun Patil 8551096333.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd