WORK ORDER

NIHVA TECHNOLOGIES PVT. LTD.

Client:	
ECO Build	
Address:	
G-1, Pride Meridian , 3-A, Shri Nagar-NX, Indore - 452018	

PO Number:	**PO-NIHVA_SRF-02032022**	**W. O. No-**	**SO/21-22/0130**
PO Dated :	**04-03-2022**	**W. O. Date**	**04-03-2022**
PO Received Date:	**04-03-2022**	**Sales Co ordinator**	**Shailesh**
Ref. Quotation:	**SQT.21.22.0197R6**	**Front Sales Person**	**Shrikant**

Dispatch Address:

ECO Build C/o SRF Limited
Near Bridgestone, Sector - 03, Industrial Area,
Pithampur, Dist- Dhar, M.P. 454775

A **Technical Terms:**

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	**Motorized Single Leaf Sliding Gate (16000 mm W) X (2400 mm H) RAL 7044 , Grey Silk**	Door type - Motorized Single Leaf Sliding Gate Opening Direction -Horizontal - from left to right or reverse Mounting Location area-Inside area Design Pattern - Standard Tubular Design Pattern Outer Frame Tube Sizes - 100 x 100 x 4mm MS RHS For Post - 100 x 100 x 4mm MS RHS Innear Tube - 96 mm x 48 mm MS RHS Gap Between Tubes - 90 mm Bottom Rail on ground - dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams Bottom Rollers -Heavy Duty Bottom Wheel With both side Bearings Guide Rollers supporter during Gate movement - Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate Painting - 2 Coats of EPOXY polyamide based enamel finish of approved colour El motor make - (100% imported) European Make Emergency Operation -Manual after turn the switch Operating Switch - Push Button from inside with 20 meter wire. Safety - Photocells, Flashing Light Civil work - Client scope – client need to grout the I beam in concrete to create track for sliding gate	**Nos**	**3**			**0**	**Pending**
2	**Manual Bi-Parting Wicket Gate (4000 mm W) X (2400 mm H)RAL 7044 , Grey Silk**	Door type - Manual Bi-Parting Wicket Gate Mounting Location area - Inside Design Pattern - Standard Tubular Design Pattern Outer Frame Tube Sizes - 100 x 100 x 4mm MS RHS Internal Vertical Tube Sizes - 96 mm x 48 mm MS RHS Gap Between Tubes - 90 mm C/C Painting - 2 Coats of EPOXY polyamide based enamel finish of approved Colour Operation - Manually Opening	**Nos**	**1**			**0**	**Pending**
3	**Manual Bi-Parting Wicket Gate (2000 mm W) X (2400 mm H)RAL 7044 , Grey Silk**	Door type - Manual Single Leaf Wicket Gate Mounting Location area - Inside Design Pattern - Standard Tubular Design Pattern Outer Frame Tube Sizes - 100 x 100 x 4mm MS RHS Internal Vertical Tube Sizes - 96 mm x 48 mm MS RHS Gap Between Tubes - 90 mm C/C Painting - 2 Coats of EPOXY polyamide based enamel finish of approved Colour Operation - Manually Opening	**Nos**	**1**			**0**	**Pending**
						Total		

Non standard items/extra requirement, if any:	

B	**Commerical Terms:**			
1	**Payment Terms:**	**40% Advance along with confirm purchase order, 40% before dispatch and 20% after installation.**		
2A	**Delivery Date as per PO:**	**Delivery of ISMC and MS Bright Bar - 06.03.2022** **Installation of Bright Bar / ISMC - 08.03.2022 to 14.03.2022** **Gate Delivery - 20.03.2022** **Installation - 25.03.2022 to 30.03.2022**	**2B. Required Delivery Date:**	
3A	**Transportation Scope:**	**In NIHVA Scope**	**3B. Transportation Charges:**	
4	**P&F Charges:**	**NIL**		
5A	**Loading Scope:**	**In NIHVA Scope**	**5B. Loading Charges:**	
6A	**Unloading Scope:**	**In Client Scope**	**6B. Unloading Charges:**	
7A	**Lifting Equipments Scope:**	**In Client Scope**	**7B. Available Lifting Equipments:**	
8	**Warranty:**	**24 Months from date of Supply**		
9A	**Height arrangement Scope:**	**In Client Scope**	**9B. Available Equipments for working at Site:**	
10	**Electricity Supply:**	**In Client Scope**		
11	**GST:**	**18%**		
12A	**Installation Scope:**	**In NIHVA Scope**	**12B. Installation required date:**	
13	**Mode of import:**	**NA**		
14	**HSS:**	**NA**		
15	**Documentation Required:**	**Standard Handover Documents**		
16A	**Total site visits required:**		**16B. Site visit charges:**	

Certified that the above work order finalised in presence of:

AGM	SALES		Operation	PROJECT	DESIGN	Date & Time
A.K.	**V.T.**		**S.B.**	**S.M.**	**G.P.**	**04-03-2022**