NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

RMK Infrastructure
RMK Square Shop No. 2992/1,Vishnupuri ,
Near Nutan Polytechnic Collage,
Talegaon Chakan Road, Talegaon Station
Tal. Maval Dist. Pune.

Date : 28.12.2020
Quote NO : SQT.20.21.2915
Kind Attn : Mr.Nagesh Sagar
Email Id : billing_tippl@rmkinfrastructure.com
Contact No: 7030967105

Subject : Quotation for Albany High Speed Door & MS Motorised Rolling Shutter .

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**ASSA ABLOY Make Rapid Roll Up Door RR300 (100% Imported From Germany)**	4000	4000	1	638,000	638,000	15,000	15,000
2	**MS Motorised Rolling Shutter**	3500	4000	1	124,000	124,000	15,000	15,000
3	**MS Motorised Rolling Shutter**	4000	4000	1	134,000	134,000	15,000	15,000
			Total			**896,000**		**45,000**
	P&F Charges			3%		**26,880**		
	Total Without Taxes					**922,880**		**45,000**
	GST Extra @ 18%			18%		166,118		8,100
	Total With Taxes					**1,088,998**		**53,100**
	Transportation Charges					**Extra at actual**		
	Unloading Charges @ Site					**In Client Scope**		


NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification





Albany Make Rapid Roll Up Door

Sr. No	Description	Specifications
1	Structure	Galvanized steel
2	Reinforcement Colours	8 standard colors - white, yellow, green, orange, red, gray, black, blue
3	Safety	• Photocells in side columns • Flexible soft bottom edge • electrical safety contact edge
4	Operation	Operator + control unit
5	Operating speed	Opening: up to 2.2 m/s ; Closing: 1.0 m/s with frequency converter control "MCC"
6	Wind load resistance	Class 1 (EN 12424)
7	Drive Unit	Motor IP 55, either RH or LH as an option.
8	Power Consumption	0.75 kw Motor
9	Curtain	Fabric Transparent PVC section
10	Power Supply	3/N/PE 380/400/415/440/480 V; 50/60 Hz.
11	Hood Cover / Motor Cover	Galvanized steel - Nihva Make
12	Control Unit	Frequency converter MCC with infomation display including foil keys open-stop-close; with main switch in separate box incl. power cable (standard length = height of door).

MS Motorised Rolling Shutter

Sr .No.	Specification	MS Motorized Rolling Shutter - Direct Drive
1	**Description:**	Motorised Rolling Shutter with MS Slats with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0 mm thick GI.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." T" Shaped profile.
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Dia -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm
12	**Control Panel**	Push button on both side
12	**Surface finish**	Synthetic Enamel Finish
13	**Drive Unit & Mounting Type**	Electric Motor - In-direct Mounting - Sprocket chain arrangement – IP54 Protection(European Make)

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 12-13 Weeks for High Speed Door & 8-9 Weeks for MS Motorised Rolling Shutter from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat -7410169333**

With Best Regards
Pradeep Shinde
7219206333
For NIHVA Technologies Pvt Ltd