NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

JMC PROJECTS (INDIA) LIMITED
C/o. NATIONAL MINERAL DEVELOPMENT CORP.
BLOCK-B, NMDC Iron and Steel Plant,
NAGARNAR, JAGDALPUR, BASTAR,
CHHATTISGARH -494001

Date : 18.2.2020
Quote NO : SQT/19-20/2448
Kind Attn : Mr. Jaikrishna
Email Id : Jaikrishna.Menon@jmcprojects.com
Contact No: 8848299551

Subject : Quotation for Motorized Sliding Gate and Boom Barrier.(Project : NMDC)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	MOTORISED SINGLE LEAF SLIDING GATE	7500	2000	1	406,000	406,000	20,000	20,000
2	BOOM BARRIER - 6M Length	6000		3	130,000	390,000	15,000	45,000
				Total		**796,000**		**65,000**
3	P&F Charges			3%		23,880		
	Total Without Taxes					819,880		65,000
	GST Extra @ 18%			18%		147,578.40		11,700
	Total With Taxes					**967,458**		**76,700**
4	Transportation Charges					In Client Scope		
5	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA make – Motorized Sliding Gate	
Door type	Motorized Sliding Gate
Opening Direction	Horizontal - from left to right or reverse
Mounting Location area	Inside area
Design Pattern	Standard Tubular Design Pattern
Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
El motor make	BFT – Italy (100% imported)
Emergency Operation	Manual after turn the switch
Operating Switch	Push Button from inside
Safety	Photocells, Flashing Light

BOOM BARRIER
Each Boom Barrier Set include: **MICHELANGELO BT A Barrier-1No.** **• Round Boom First part-1No.** **• Round Boom Second part- 1 No.** **• Anchor Base- 1No.** **• MOB. Boom Rest-1No.** **• Rubber Safety Profile- 1No.** **• OMEGA AT Acce. - 1No.** **• Transmitter with Channels- 1No.** **• Push Button**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6-7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd