NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT.20.21.2868 **Date : 05.12.2020**

Lupin Limited
Aurangabad

Kind Attn : **Mr.Dilip Khandade**
Email : dilipkhandade@lupin.com
Contact No : 0240-6612272

Project Name And Location : Aurangabad

Subject: Quotation for High Speed Door HS9020GAT

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
1	**ASSA ABLOY Make Rapid Roll Up Door HS9020GAT** **(Supply + Installation)**				
Area of use:	Inside				
Material:	Galvanised Steel				
Colours:	8 standard colors - white, yellow, green, orange, red, gray, black, blue				
Safety:	1) Photocells in side columns 2) Flexible soft bottom edge including wireless edge activator 3) Break-away and self-repair function				
Vision Window	Single row with 400 mm Height				
Operating speed:	Opening: up to 1,2 m/s (optional 2,0 m/s) Closing: 0,5 m/s				
Wind load resistance:	Class 1 (300 Pa (N/m²)) maximum wind load while closing 50 Pa (N/m²)				
Water penetration:	Class 2 (50 Pa (N/m²))				
Air permeability:	Class 1 (24 m³/m²/h at 50 Pa)				
Thermal transmittance:	6,02 W/(m²K)				
Lifetime expectations:	1.000.000 cycles				
Temperature working range:	5 °C to +40 °C				
1	**Size:(W) 2000 mm x (H) 1900 mm**	1	No	561,000.00	561,000.00

GST Pune :	27AAECN0437H1ZM	**TOTAL BASIC AMOUNT**	**561,000.00**

Client Scope of Work:

1. Custom Duty + Custom Clearance + Local Transport, till site in clients Scope. NIHVA will handover BL to client for further all process & action till material reaches at site & unloads at required place.
2. For High Sea sale responsibility of NIHVA ceases on transfer of BL to client.
3. Client should issue required forms to NIHVA for all Tax Exemptions.

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex Works Pune
2	**P & F Charges**	:	@3 % of total supply value
3	**Delivery**	:	12-14 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
4	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch
5	**Insurance**	:	Extra As applicable
6	**Validity**	:	Validity of Offer is 15 days from the date of quotation
7	**Warranty**	:	12 months from the date of supply

For any further Clarification /Information in this Concern, Please feel free to Contact Ms. Sneha Bharane on 8551035333

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd