**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**Shapoorji Pallonji And Company Private Limited,**
Chennai

**Date : 07.01.2021**
**Quote NO : SQT.20-21.2934**
**Kind Attn :** DHIAGARAJAN.G
**Email Id :** DHIAGARAJAN.GUNASEKARAN@shapoorji.com
**Contact No:** 9750170016

**Subject : Quotation for Motorised Single Leaf Sliding Gate - Bargur Sipcot**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |

**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | Motorised Single Leaf Sliding Gate | 12000 | 1800 | 3 | 565,059 | 1,695,177 | 20,000 | 60,000 |
| 2 | Motorised Single Leaf Sliding Gate | 10000 | 1800 | 1 | 522,536 | 522,536 | 20,000 | 20,000 |
| 3 | Motorised Single Leaf Sliding Gate | 9000 | 1800 | 1 | 485,000 | 485,000 | 20,000 | 20,000 |
| 4 | Wicket Gate | 1000 | 1800 | 5 | 35,000 | 175,000 | 10,000 | 50,000 |
| | | | | **Total** | | **2,877,713** | | **150,000** |
| 5 | P&F Charges | | | 3% | | 86,331 | | |
| | **Total Without Taxes** | | | | | 2,964,044 | | 150,000 |
| | GST Extra @ 18% | | | 18% | | 533,527.99 | | 27,000 |
| | **Total With Taxes** | | | | | **3,497,572** | | **177,000** |
| 6 | Transportation Charges | | | | | Extra at Actual | | |
| 7 | Unloading Charges @ Site | | | | | In Client Scope | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

| NIHVA make – Motorized Sliding Gate | |
|---|---|
| Door type | Single Leaf Sliding Gate |
| Opening Direction | Horizontal - from left to right or reverse |
| Mounting Location area | Inside area |
| Design Pattern | Standard Tubular Design Pattern |
| Outer Tube | 100 X 50 X 4 mm THK SQ. TUBE |
| For Post | 100 X 50 X 4 mm THK SQ. TUBE |
| Inner Vertical Flat | 50 X 10 mm FLAT |
| Bottom Rail on ground | Dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams |
| Bottom Rollers | Heavy Duty Bottom Wheel With both side Bearings (chorme plated) |
| Guide Rollers supporter during Gate movement | Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate |
| Painting | 2 Coats of EPOXY polyamide based enamel finish of approved colour |
| El motor make | BFT – Italy (100% imported) |
| Emergency Operation | Manual after turn the switch |
| Operating Switch | Push Button from inside |
| Safety | Photocells, Flashing Light |
| Metal Rack | zinc plated metal rack |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description |
|---|---|
| 1 | Secured and fully covered Store area to keep the material |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site |
| 3 | Electrical Supply on the site single phase/three phase points at different places. |
| 4 | Any civil / masonry/structural work required |
| 5 | All structure support required |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. |
| 7 | Conduits, Cables required |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd