NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

KEMS AUTO COMPONETS LTD
HOSKOTE-562114,

Date : 05.03.2020
Quote NO : SQT.19-20.2372
Kind Attn : Mr. YALLAAPPA KUDACHI
Email Id : yallappa.k@kemsltd.com

Project Name & Location: Tandem Scissor Lift & Mumbai

Subject : Quotation for Tandem Scissor Lift

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**NIHVA Tandem Scissor Lift Capacity : 7 ton**	3000	5200	1	9,42,500	9,42,500	20,000	20,000
				Total		**9,42,500**		**20,000**
	P&F Charges			3%		**28,275**		
	Total Without Taxes					**9,70,775**		
	GST Extra @ 18%			18%		1,74,740		-
	Total With Taxes					**11,45,515**		**-**
	Transportation Charges					**In Client Scope**		
	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA Scissor Lift

Sr. No	Description	Specifications
1	Type of Mounting	Pit Mounted
2	Capacity	7 ton
3	Platform size	5200L x 3000W
4	Shut ht	500 mm
5	Max ht	2100 mm
6	Power pack	10HP, 3 Phase
7	Safety Railing	both length side only 800 mm height
8	Color	Golden Yellow (RAL 1004) std
9	Manual Flap	400 x 2000 x 12mm thk (Approximately)
		Up & down control panel on the scissor platform along with main panel (with 5 mtr cable) on the wall

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks for Scissor Lift from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil 8551096333.**

With Best Regards
Samruddhi
7410175333
For NIHVA Technologies Pvt Ltd