NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Unioteq Commercial Services Pvt. Ltd.
Aurangabad

Date : 22.06.2021
Quote NO : AS_21.22.0017
Kind Attn : Mr. Ganesh Deshmukh
Email Id : ganesh@unioteq.com
Contact No: 9028283553

Project Name & Location: Unioteq Commercial Services Pvt. Ltd., Aurangabad

Subject : Commercial Offer for Slat Chain Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size	Qty	Supply Charges in INR		Installation Charges in INR	
		Length (in mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Slat Chain Conveyor**	10000	1	4,99,500	4,99,500	20,000	20,000
			Total		**4,99,500**		**20,000**
		P&F Charges on Total Supply Value	3%		**14,985**		
		Total Without Taxes			**4,99,500**		**20,000**
		GST Extra @ 18%	18%		89,910		3,600
		Total With Taxes			**5,89,410**		**23,600**
2		Transportation Charges					**Extra At Actual**
3		Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification -

Slat Chain Conveyor

Sr. No	Description	Specifications
1	Product	Automobile parts
2	Contact parts	MS
3	Non-Contact parts	MS
4	Gear-motor	Bonfiglioli
5	Speed adjustment	Through VFD
6	Caster wheel	Nylon wheels
7	Infeed height	700 mm
8	Length of conveyor	10 mtr
9	Movable conveyor	NO
10	Belt make	Spectra
11	Belt type	Metalic
12	Conveyor speed	5 to 6 mtr per min
13	Total weight on conveyor	300 kg max

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or Written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material.
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site.
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required.
5	All structure support required.
6	In Case of any changes in the layout as per site requirements after the shipment of material, the additional quantities and the wastage.
7	Conduits, Cables required.

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 7 -8 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact Mr. Rohit Kadgave 7410175333

With Best Regards

Pratibha Mete
8530872333

For NIHVA Technologies Pvt Ltd