NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Prime Sorce Group
Saudi Arabia

Date : 08.12.2021
Quote NO : **AS_21.22.0013**
Kind Attn : Mr. Omar Dehwah
Email Id : opo@psgsa.com.sa
Contact No:

Project Name & Location: Prime Sorce Group, Saudi Arabia

Subject : Quotation for Palletizer Machine

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Palletizer Machine** • Number of boxes in pallets 197x155x145 mm – 315 Box/Plt – 35 BOX x 9 Layers 197x155x145 mm – 245 Box/Plt – 35 BOX x 7 Layers 285x235x205 mm – 68 Box/Plt – 17 BOX x 4 Layers 197x150x105 mm – 576 Box/Plt – 48 BOX x 12 Layers	**1**	**28,50,000**	**28,50,000**	**75,000**	**75,000**
		Total		**28,50,000**		**75,000**
	P&F Charges	3%		**85,500**		
	Total Without Taxes			**29,35,500**		**75,000**
2	GST Extra @ 18%					**Extra At Actual**
3	All custom duties and transport charges					**Extra At Actual**
4	Insurance Charges					**Extra At Actual**
5	Unloading Charges @ Site					**In Client Scope**
6	**Note: Please note all these boxes are considered to pass through one palletizer.**					
7	**Note: Quoted value mentioned above is in Indian rupees only.**					

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification & Sequence of Operation

Sr. No.	Component	Application
1	Box transfer unit	Grid formation is place on this unit from where it tranfers to pallet.
2	Lift conveyor	For placing box conveyor one above the other.
3	Box transfer roller conveyor	Single boxes froms grid on this conveyor.
4	Box pusher unit	Formed box grid conveyor on rollar conveyor is tranferred vis this pusher unit
5	Pallet tranfer chain conveyor	To transfer pallet to appropriate location.
6	Pallet dispenser	Stack of 5 pallet is collected on this conveyor & released one by one.
7	Control panel	All automation is controlled from control panel
8	Main control panel	Floor mounted cabinet Sixe: 1200 X 500 X 1500 (LXWXH)
9	MCB	Siemens
10	PLC	Siemens
11	VFD	Siemens
12	HMI	5" HMI, Siemens
13	Power Supply	Omron
14	Structure	Powder coated/Chrome plating

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 After 1 year, non-comprehensive AMC will be provided by NIHVA which is at an extra cost.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8-10 weeks from the date of receipt of confirmed Purchase order, Advance payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance 20% against readiness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Vijay Tarak on 85510 93333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd